

AD-A085 024


SCIENTIFIC SERVICE INC REDWOOD CITY CA
SHELTER UPGRADING MANUAL: HOST AREA SHELTERS. (U)

F/6 13/13

UNCLASSIFIED

MAR 80 C WILTON, B L GABRIELSEN, R S TANSLEY DCPA01-78-C-0215
SSI-7815-8 NL

1 of 3
ADA
085 024



LEVEL II

10

SSI 7815-8

March 1980

ADA 085024

shelter upgrading manual: host area shelters

FINAL REPORT

DTIC
2000 0000

Approved for public release:
distribution unlimited

Contract No. DCPA01-78-C-0215
Work Unit 1127H

SCIENTIFIC SERVICE, INC.

DDC FILE COPY

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, contractors, subcontractors, or their employees, makes any warranty, express or implied, nor assumes any legal liability or responsibility for any third party's use or the results of such use of any information, apparatus, product or process disclosed in this report, nor represents that its use by such third party would not infringe privately owned rights.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER 14 SSI-7815-8	2. GOVT ACCESSION NO. AD A085 024	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) SHELTER UPGRADING MANUAL: HOST AREA SHELTERS,	5. TYPE OF REPORT & PERIOD COVERED Final Report,	
7. AUTHOR(s) C. Wilton, B.L. Gabrielsen, and R.S. Tansley	8. CONTRACT OR GRANT NUMBER(s) DCPA01-78-C-0215	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Scientific Service, Inc. 517 East Bayshore, Redwood City, CA 94063	10. PROGRAM ELEMENT PROJECT TASK AREA & WORK UNIT NUMBERS Work Unit 1127H	
11. CONTROLLING OFFICE NAME AND ADDRESS Federal Emergency Management Agency Washington, DC 20472	12. REPORT DATE 11 March 1980	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	13. NUMBER OF PAGES 221	
	15. SECURITY CLASS (of this report)	
	15a. DECLASSIFICATION DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary, and identify by block number) blast protection; civil defense; crisis relocation planning; fallout protection; host area; manual; shelter; upgrading		
20. ABSTRACT (Continue on reverse side if necessary, and identify by block number) → The manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, and without adequate shelter, crisis relocation planning is not viable. This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings;		

DD FORM 1473 1 JAN 73 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified
SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

80 6 2 113

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

20. ABSTRACT (contd)

develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; develops a framework for the practical use of the manual by all persons of interest; and contains charts, pictorial representations, and worksheets that complement and simplify the utility of the manual.

The information contained herein is supported by a test program, DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.

The manual is in looseleaf form to permit removal of pertinent worksheets and charts for developing upgrading plans for a specific building, and to permit the addition of new and replacement material as the work progresses.

4.

Accession For	
WTIS 00001	
DDC TAB	
Unannounced	
Justification	
By	
Dist	
Avail	
Dist	Avail and/or special
A	

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SSI 7815-8 Final Report
March 1980

(DETACHABLE SUMMARY)

Approved for public release;
distribution unlimited

SHELTER UPGRADING MANUAL: HOST AREA SHELTERS

by
C. Wilton, B.L. Gabrielsen, R.S. Tansley

for

Federal Emergency Management Agency
Washington, D.C. 20472

Contract No. DCPA01-78-C-0215, Work Unit 1127H
Dr. Michael A. Pachuta, COTR

FEMA REVIEW NOTICE:

This report has been reviewed in the Federal Emergency Management Agency and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Federal Emergency Management Agency.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, contractors, subcontractors, or their employees, makes any warranty, express or implied, nor assumes any legal liability or responsibility for any third party's use or the results of such use of any information, apparatus, product or process disclosed in this report, nor represents that its use by such third party would not infringe privately owned rights.

Scientific Service, Inc.
517 East Bayshore, Redwood City, CA 94063

This manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, for without adequate shelter, crisis relocation planning is not viable.

This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings; develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; and develops a framework for the practical use of the manual by all persons of interest. The information contained herein is supported by a test program, under Contract No. DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.

Sections of the manual assist in the selection and identification of potential shelter facilities, explain the use of the manual and the selection of upgrading methods, contain charts on the upgrading of various floor and roof systems, and present sketches of the upgrading methods and the resources required for each method. Worksheets and the necessary charts for sizing the shoring or other materials required for each method complement and simplify the utility of the manual. Also included are appendices that assist in the evaluation of a structure for use as a potential shelter, show data and charts for closing small openings, and illustrate alternative types of shoring systems.

The manual is in a looseleaf format so that worksheets and data sheets can be removed to develop upgrading plans for a specific structure. This format will also allow for the insertion of new data and sections as they become available.

SSI 7815-8 Final Report
March 1980

Approved for public release;
distribution unlimited

SHELTER UPGRADING MANUAL: HOST AREA SHELTERS

by
C. Wilton, B.L. Gabrielsen, R.S. Tansley

for
Federal Emergency Management Agency
Washington, D.C. 20472

Contract No. DCPA01-78-C-0215, Work Unit 1127H
Dr. Michael A. Pachuta, COTR

FEMA REVIEW NOTICE:

This report has been reviewed in the Federal Emergency Management Agency and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Federal Emergency Management Agency.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, contractors, subcontractors, or their employees, makes any warranty, express or implied, nor assumes any legal liability or responsibility for any third party's use or the results of such use of any information, apparatus, product or process disclosed in this report, nor represents that its use by such third party would not infringe privately owned rights.

Scientific Service, Inc.
517 East Bayshore, Redwood City, CA 94063

Table of Contents

SECTION 1	Introduction
SECTION 2	Selection and Identification of Potential Shelter Facilities
SECTION 3	Selection and Implementation of Upgrading Schemes
SECTION 4	Floors
SECTION 5	Roofs
SECTION 6	Illustrations
SECTION 7	Worksheets
SECTION 8	Charts
APPENDIX A	Evaluation of Potential Shelter Facilities
APPENDIX B	Closures
APPENDIX C	Alternative Shoring Systems

Glossary and List of Notations

As built —	Structure prior to upgrading	psf	pounds per square foot
Host area —	Area that is subjected to blast pressures of 2 psi or less	psi	pounds per square inch
Key worker area —	Area that is subjected to blast pressures greater than 30 psi	kPa	kilopascal (psi times 6.895)
Overpressure —	Pressure caused by blast	S_R	survival rating
Protection factor —	Factor that compares degree of radiation protection to zero protection	P_f	protection factor
Protection factor key —	Earth thickness in feet required to obtain specified radiation protection	I	shelter rating - 40 psi overpressure
Risk area —	Area that is subjected to blast pressures from 2 psi to 30 psi	II	shelter rating - 30 psi overpressure
Shelter rating —	Rating given a shelter, in roman numerals, corresponding to a given overpressure (see Fig. 1-1)	III	shelter rating - 20 psi overpressure
Survival rating —	95% probability of survival for a structure of a given shelter rating	IV	shelter rating - 10 psi overpressure
		V	shelter rating - 5 psi overpressure
		VI	shelter rating - 2 psi overpressure
		VI ⁺	slightly better than a VI shelter rating (used for all shelter ratings)
		VI ⁻	slightly less than a VI shelter rating (used for all shelter ratings)
		N	no additional radiation protection required
		"0"	provides no blast survival
		+	depth of earth required for radiation protection would cause collapse

SECTION 1- Introduction

SECTION 1

INTRODUCTION

Section 1 INTRODUCTION

This manual is intended for use in the identification of and the upgrading, if required, of shelter spaces to support Crisis Relocation Planning. Concern is limited here to shelters in the "host" areas, where it is assumed blast overpressures do not exceed 2 psi and radiation protection equivalent to 18 in. of earth is adequate.

The manual is organized as follows: Section 2 will assist in the selection and identification of potential shelter facilities. Section 3 explains the use of the manual and the selection of methods for upgrading with examples. Sections 4 and 5 contain the key charts on the upgrading of various floors and roofs. Section 6 contains sketches of the various upgrading methods and the resources required for each. Section 7 has the various worksheets for each method. Section 8 includes the charts necessary for sizing the shoring required for the upgrading method selected. At the end of the manual, appendices containing supplemental information are provided. Appendix A assists in the evaluation of a structure for use as a potential shelter. Appendix B provides data and charts for closing small openings. Appendix C illustrates alternative types of shoring systems.

The manual is in looseleaf format for two reasons: (1) Use of the manual requires that worksheets and data sheets be removed to develop upgrading plans for a specific building; and (2) In its present form the manual is far from complete, and replacement or new pages and sections, which are being developed by SSI, will be supplied for insertion when available. Included in this new information will be additional upgrading schemes for floors and roofs, based on upcoming full-scale tests of floor and roof systems;

procedures for upgrading walls of aboveground shelters; a more extensive closure section; and the necessary information for calculating required supplemental equipment such as ventilation, water and sanitation kits.

It should also be noted that the manual is one of a series that will also consider key worker and risk area shelters. In these other manuals higher overpressures will be considered, and shelters will be ranked by survival ratings "as built" and for the various upgrading schemes. Shelters will be rated for selected overpressures, and each shelter rating will carry a roman numeral designation corresponding to a particular overpressure. A pictorial representation of the relationship between shelter rating, overpressure, and the key worker, risk, and host areas is shown in Fig. 1-1. As mentioned above, this manual confines itself to VI shelter rating or a maximum of 2 psi overpressure, which is defined as a host area shelter.




Fig. 1-1. Comparison of Overpressure and Shelter Rating Required.

SECTION 2 - Selection of
Shelter Facilities

SECTION 2

SELECTION AND IDENTIFICATION OF POTENTIAL SHELTER FACILITIES

Section 2

SELECTION AND IDENTIFICATION OF POTENTIAL SHELTER FACILITIES


INTRODUCTION

The objective of this section of the manual is to describe a simple method for evaluation and selection of the potential shelter facility; i.e., building or portion thereof. The charts used in this manual have been simplified and are conservative. By conservative it is meant that 95% of the building elements are better than the rating provided; conversely, it has been assumed that a 5% probability of collapse is an acceptable risk level.

The initial evaluation and selection process is based on "intended use" code-based design criteria. With few exceptions, most buildings constructed during the past 50 years were designed using some type of building code, either national or local codes, which are usually adaptations of the national codes. These codes specify the minimum design standard for each of the building elements; i.e., floors, walls, and roofs. See Appendix A for assistance in the evaluation of potential shelter facilities.

Since a host area shelter will probably only be exposed to a blast overpressure of 1 or 2 psi, a variety of aboveground as well as basement shelters can be used. Also a host area, or VI rated, shelter needs to be strong enough to support the necessary fallout protection. This has led to the use of both a protection factor (P_f) rating and a survival (S_R) rating for each of the structural components and upgrading techniques used in this manual. The protection factor key relates to fallout radiation protection factors of 40, 100, and 1000, and indicates the depth of earth in feet, or equivalent, required to achieve that particular radiation factor. "N" indicates that no additional radiation protection is required since the mass of the structural element is adequate protection for the P_f listed.

The equivalent radiation protection of 1, 1.5, and 3 ft of earth (assumed weight = 100 pcf) may be achieved by use of alternative materials. The chart below indicates the relationship in inches between five common materials and earth. For example, 12 in. of earth is equal in radiation protection to 8 in. of concrete, 2½ in. of steel, etc.



FLOOR SYSTEM ANALYSIS

The design criteria for floors are specified as the recommended minimum floor live loads as a function of the original intended use of the structure. A table of minimum floor loads is shown in Table 2-1. Thus, if the original intended use and the type of construction (i.e., wood, steel, or concrete) are known, it is possible to establish collapse loads for the floor system. This is demonstrated in Table 2-2, which gives the collapse load for light, medium, and heavy design floors for the four most common types of construction—wood, light steel, heavy steel, and concrete. These data can then be used to derive the "as built" floor Safety Rating table shown in Table 2-3. This table indicates whether or not the "as built" floor is strong enough to sustain a 2 psi blast with 18 inches of soil ($P_f = 100$) for radiation protection, or a Survival Rating of VI. If the floor will not meet the criteria of an $S_p = VI$, as built, upgrading is required. Section 3 should be consulted for assistance in the selection of upgrading schemes. As an example, note that wood constructions, light and medium, will not support the required blast load plus the radiation protection as built, and will require upgrading. Heavy wood construction is "OK" as built.

Halls and corridors are usually designed to support a live load equal to the occupancy loading that they serve, with some minor exceptions as shown in Table 2-1, and therefore, may be upgraded as a floor. The walls of halls and corridors should be carefully evaluated to assure that they are, in fact, bearing walls and that the short span encountered between the walls is actually the span to be considered in the upgrading determination. In many cases, only one of the walls is a bearing wall, and the span across the corridor is an extension of the span of the adjacent room, with a non-load-bearing partition separating the corridor from the room. In this case, the room and corridor spans would be added together to determine the length of the span to be considered.

Table 2-1

DESIGN INFORMATION: RECOMMENDED MINIMUM FLOOR LIVE LOADS

UNIFORMLY DISTRIBUTED LOADS

UNIFORMLY DISTRIBUTED LOADS		UNIFORMLY DISTRIBUTED LOADS		UNIFORMLY DISTRIBUTED LOADS	
Occupancy or Use	Live Load (psf)	Occupancy or Use	Live Load (psf)	Occupancy or Use	Live Load (psf)
Apartments (see Residential)	150	Office buildings:	50	Stores:	100
Armories and drill rooms	60	Offices	100	Retail:	75
Assembly halls and other places of assembly:	100	Lobbies	80	First floor, rooms	125
Fixed seats	100	Corridors, above first floor	40	Upper floors	100
Movable seats	75	File and computer rooms require heavier loads based upon anticipated occupancy	100	Wholesale	150
Platforms (assembly)	100	Penal institutions:	40	Theaters:	100
Bowling alleys, poolrooms, and similar recreational areas	100	Cell blocks	100	Aisles, corridors, and lobbies	60
Corridors:	100	Corridors	40	Orchestra floors	60
First floor	100	Residential:	40	Balconies	100
Other floors, same as occupancy served except as indicated	100	Multifamily houses:	40	Stage floors	150
Dance halls and ballrooms	100	Private apartments	100	Yards and terraces, pedestrians	100
Dining rooms and restaurants	100	Public rooms	80		
Dwellings (see Residential)	50	Corridors	40		
Garages (passenger cars only)	100	Dwellings:	40		
Grandstands (see Reviewing stands)	100	First floor	30		
Gymnasiums, main floors and balconies	100	Second floor and habitable attics	20		
Hospitals:	60	Uninhabitable attics	40		
Operating rooms, laboratories	40	Hotels:	40		
Private rooms	40	Guest rooms	100		
Wards	40	Public rooms	100		
Corridors, above first floor	80	Corridors serving public rooms	80		
Hotels (see Residential)	60	Corridors	100		
Libraries:	150	Reviewing stands and bleachers	40		
Reading rooms	80	Schools:	80		
Stack rooms (books & shelving at 65 pcf) but not less than	125	Classrooms	125		
Corridors, above first floor	250	Corridors	250		
Manufacturing:		Sidewalks, vehicular driveways, and yards, subject to trucking	100		
Light		Skating rinks	100		
Heavy		Stairs and exitways	100		
		Storage warehouse:	125		
		Light	250		
		Heavy	250		

DESIGN LOAD GROUPS
(as used in this manual)

LIGHT:

40 to 60 psf

MEDIUM:

80 to 125 psf

HEAVY:

150 to 250 psf

Table 2-2
FLOOR SYSTEM COLLAPSE LOADS ⁽¹⁾ psf (psi)

Floor Type and Dead Load (D.L.)	Live Load		
	LIGHT (L) 50 psf (40 - 60 psf)	MEDIUM (M) 100 psf (80 - 125 psf)	HEAVY (H) 200 psf (150 - 250 psf)
Wood (W) Construction (D.L. = 20 psf)	120 (0.8) soil ⁽²⁾ 200 (1.4) blast ⁽³⁾	220 (1.5) soil ⁽²⁾ 367 (2.6) blast ⁽³⁾	420 (2.9) soil ⁽²⁾ 700 (4.9) blast ⁽³⁾
Steel, Light (SL) Construction (D.L. = 30)	105 (0.7)	190 (1.3)	does not exist
Steel, Heavy (SH) Construction (D.L. = 80)	140 (1.0)	225 (1.6)	395 (2.8)
Concrete (C) Construction (D.L. = 100)	200 (1.4)	300 (2.1)	500 (3.5)

Notes

- (1) Safety factors are 2.0, 1.7, and 2.0 for timber, steel, and concrete, respectively. The 1.7 for steel assumes a truss support system.
- (2) Static load (soil)
- (3) Dynamic load (blast)

Table 2-3
FLOOR SAFETY RATING TABLE FOR AS BUILT CONSTRUCTIONS
WITH $P_f = 100$ (18 in. soil) AND $S_R = VI$ (2 psi)

Type	Loading	Light 50 psf (40 - 60 psf)	Medium 100 psf (80 - 125 psf)	Heavy 200 psf (150 - 250 psf)
Wood Construction		Upgrading required, see Section 3	Upgrading required, see Section 3	"OK" as built
Steel Light Construction		Upgrading required, see Section 3	Upgrading required, see Section 3	Does not exist
Steel Heavy Construction		Upgrading required, see Section 3	Upgrading required, see Section 3	"OK" as built
Concrete Construction		Upgrading required, see Section 3	Upgrading required, see Section 3	"OK" as built

ROOF SYSTEM ANALYSIS

A similar analysis can be applied to roof systems. It is assumed that the roof systems of interest are relatively flat and that the radiation upgrading can be accomplished by adding soil. Table 2-4 provides the results of the analysis in force units.

There are no roof systems that, without upgrading, will have an $S_R = VI$ (2 psi plus 18 in. soil). Refer directly to Section 3 of the manual for the appropriate methods of upgrading.

Table 2-4

ROOF SYSTEM ANALYSIS

Column 1	Column 2	Column 3	Column 4	Column 5
Roof Type	Design Live Load	Design Dead Load	Design Safety Factor	Collapse ⁽⁴⁾ Load ⁽⁵⁾
	psf	psf	psf	psf (psi)
Wood (W)	15	15	2.0	45 (0.3) soil 75 (0.5) blast
Steel ⁽¹⁾ (SL) Light Con- struction	15	25	1.7 (3)	45 (0.3) soil or blast
Steel ⁽²⁾ (SH) Heavy Con- struction	15	60	1.7 (3)	65 (0.4) soil or blast
Concrete (C)	15	80	2.0	110 (0.8) soil or blast

Notes

- (1) Light steel construction assumes a steel support structure and a timber sheathing system.
- (2) Heavy steel construction assumes a steel support structure, steel decking and a lightweight concrete topping.
- (3) The 1.7 safety factor assumes truss supports. Beams will provide a higher safety factor.
- (4) The collapse load values shown in Column 5 can be increased in snow regions by multiplying the regional design snow load minus 15 psf by the safety factor and adding to Column 5.
- (5) If a roof structure is used for parking or some other activity, analyze it as a floor system.

WALL SYSTEM ANALYSIS

Wall systems can also be analyzed in a similar manner. The majority of wall systems can be grouped into three basic categories, as shown in Table 2-5. With regard to blast loading, the design criterion of interest is wind load, which is typically 20 psf. Taking into account the common safety factor of 2, the minimum collapse load for wall systems is 40 psf, or 0.3 psi, as shown in Table 2-6.

Observe that only the most massive walls offer any radiation protection, and only certain ones of those (masonry, brick and concrete infill) provide very minor blast protection. In addition, of course, all window and door openings must have closures added, except as required for ventilation. See Appendix B for methods of closing small openings.

Table 2-5
WALL SYSTEMS

<u>Light</u> (weight: 10 to 25 psf)	<u>Heavy</u> (weight: greater than 80 psf)
Timber stud (stucco, plywood, etc.)	Stone
Tile (clay)	8-inch concrete block/brick face
Metal stud	12-inch brick
Glass (steel or aluminum frame)	8-inch concrete
Steel or aluminum panels	
Plastic (fiberglass/foam)	
Asbestos cement	
<u>Medium</u> (weight: 25 to 80 psf)	
Concrete block (non or partially grouted)	
8-inch brick walls	
4-inch brick	
4-inch brick plus 4-inch block or stud	

Table 2-6
WALL SYSTEM COLLAPSE LOADS psf (psi)

Wall Type	Design Load	Safety Factor	Collapse Load
Light	20	2.0	40 (0.3)
Medium	20	2.0	40 (0.3)
Heavy	20	2.0	40 (0.3) ⁽¹⁾

Note

- (1) When the 12-in. brick and/or 8-in. concrete are built into (infilled) a heavy concrete frame building, this number is 150 psf or 1 psi.

*SECTION 3 - Selection of
Upgrading Schemes*

SECTION 3

SELECTION AND IMPLEMENTATION OF UPGRADING SCHEMES

Section 3
SELECTION AND IMPLEMENTATION OF UPGRADING SCHEMES

INTRODUCTION

This section will describe the use of the following sections of the manual in the selection and implementation of an upgrading scheme for the shelter facility selected and identified under Section 2. Included with a description of each of the subsequent sections are examples in the use of the charts, worksheets, illustrations and resource lists.

DESCRIPTION OF SECTION CONTENTS

Sections 4 and 5 are entitled Floors and Roofs, respectively. Each of these sections contains illustrations of typical floor and roof systems in "as built" configurations; that is, as they would appear prior to upgrading. Each of the illustrations has a short paragraph adjacent to it with information on use, spans, and design loading, which further helps the user to identify the system. Additionally, each system has a small inset chart that lists the radiation P_f (protection factor) and key (feet of earth consistent with the protection factor) and the S_R (survival rating) for the particular system "as built." Facing each of the "as built" illustrations is a chart listing the shoring systems applicable to that particular type of construction. This chart also indicates the upgraded Key and S_R for each upgrading scheme, and directs the user to the appropriate illustration of the selected scheme, the charts required for determination of the shoring size and spacing, and the particular worksheet to be used for implementation of the upgrading scheme.

Section 6 contains the illustrations of all the various upgrading schemes and provides a checklist of resources required for each, and Section 7 contains the worksheets for each scheme. Section 8 contains the required charts for shore size and spacing.

EXAMPLE OF MANUAL USE

The user, after reading Section 2 and referring to Appendix A if necessary, has selected a residential basement for a shelter. He observes that the construction type is timber joist and, since the structure was originally built as a residence, he can reasonably assume that the design floor load is "light," as defined in Table 2-1. With this information, the user proceeds to Section 4 and refers to the index in front of the section. Under "Wood Construction — Floor, Timber Joist — light design" he is referred to page 4-1, which contains a sketch of a timber joist floor, some descriptive information, and the survival ratings (S_R) of the "as built" floor with various degrees of radiation protection (P_f). The sketch and description are similar to the intended shelter, but indicate that a radiation protection factor (P_f) of 40 (one foot of earth) would reduce the blast protection, or survival rating (S_R), to "0", and a $P_f = 100$ (1.5 ft of earth) would cause collapse (+). It is apparent, therefore, that if this selected structure is to be used as a shelter, it requires upgrading.

Facing the page containing the "as built" sketch is a chart listing the various types of upgrading schemes that may be applied to this type of construction. A review of this chart indicates that all these schemes will support significant radiation protection, $P_f = 100$ with 2 psi blast protection, $S_R = VI$. An upgrading system should be selected from this list. It is suggested that the illustrations, details, and required resources of each scheme be reviewed prior to making a selection. (If the amount of open floor area is a consideration, several schemes, such as King Post Truss, Flange, and Boxed Beam upgrading, are better suited to maximizing open floor area.) For this example, assume that the user has selected a wood stud wall at midspan as an upgrading scheme. He should then remove the indicated illustration and detail page along with the facing resource list from Section 6, the worksheet from Section 7, and the chart from Section 8. In this case he would remove from the manual: page 6-1, Section 6 (and facing page); page 7-1, Section 7; and page 8-1, Section 8.

An example of the completed worksheet is shown in Fig. 3-1, and the chart used is shown on Fig. 3-2. The timber required — in this case, 324 linear feet of 2 x 4's — should be entered on the resource list. The resources checklist should be consulted for the additional resources required: bracing, hammer, nails, etc.


In this example, let us assume that the full basement is actually 36 ft x 24 ft and that the joists are supported at mid-width of the basement by a light steel beam, which is in turn supported by a steel pipe column, at mid-length. This is the condition outlined in Item No. 6 on Worksheet A, and requires the use of Worksheet G, page 7-7, Section 7, to determine post shores required for the steel beam.

Fig. 3-3 shows Worksheet G completed, and Fig. 3-4 shows the chart used with this worksheet. The quantity of posts required should be listed on the resource sheet.

It should be remembered that the quantity of wood studs should be doubled if both sides of the basement are to be upgraded. However, if only one side is to be upgraded, it is still necessary to shore the steel beam at mid-length, as shown in Fig. 3-3.

Appendix B gives assistance on closing small openings (doors, windows, ventilators, etc.) and Appendix C suggests some alternative types of commercial shores, which, if available, might be used.

WORKSHEET A stud wall upgrading



L 36' W 12' H 8'

1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided above. These dimensions need not be exact - the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.

2. Sketch in the figure above the intended location of the stud wall(s). If one wall is used, it should be located at midspan along dashed line (W/2) and if two are used, at 1/3 span (W/3) along dotted lines. The wall(s) should be continuous the full length (L) of the area.

3. Determine the distance (X) from the stud wall to the adjacent support (wall, beam, other stud wall, etc.).

X = 6 ft

4. With (X) and (H) from above, go to Chart A, page 8-1, Section 8, to determine the timber size required; enter

Chart A from left with (X) and read over to ceiling height (H). Read above intersection point to find the size of studs and spacing that may be used.

Stud Size 2 in. by 4 in.
at 16 in. on center.

5. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

Studs 2 in. by 4 in.

H 8 ft x L 36 ft x 12 = 216 lin. ft
16 in. on center

Top Plates (same size as studs,
two required)

L 36 ft x 2 = 72 lin. ft


Bottom Plate (same size as
studs, one required)

L 36 ft x 1 = 36 lin. ft

Total Timber Required = 324 lin. ft

Note: If two walls are used, double the above timber requirement. Enter size and linear feet of timber required on the Resources List.

6. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 - Beam Shoring, to determine post shores required.




STUD WALL DATA

FIG. 3-2

A

WORKSHEET G beam shoring



1. This Worksheet is to be used when the existing ceiling support(s) are beams in lieu of bearing walls. These beams require upgrading with timber posts.
2. Measure the intended shelter area. Fill in the length (L) , widths $(W_1$ and $W_2)$, and height (H) of the area in the spaces provided above. These dimensions need not be exact — the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.
3. Sketch in the figure above the intended location of the posts along the existing beam. They should be located symmetrically at $L/2$, $L/3$, or $L/4$.

FIG. 3-3

3-6

4. Determine the distance between the posts (Y) . $36/4 = 9$

$$Y = 9 \text{ ft}$$

Calculate (X) .

$$\frac{W_1 + W_2}{2} = X = 6 \text{ ft}$$

Multiply $X \times Y$ $9 \times 6 = 54$ sq ft supported area

5. With the supported area and (H) from above, go to either Chart B, page 8-2, or Chart D, page 8-4, Section 8, to determine the timber post size required. Use Chart B if the post is supporting a timber beam and Chart D if the post is supporting a beam other than timber (steel, concrete, etc.). Enter the appropriate chart from the left with the supported area and read over to ceiling height. Read above the intersection point to find the size of timber posts that may be used.


Post Size 4 in. by 6 in.

6. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

Post 4 in. by 6 in.

No. of Posts 2 x H 8 ft = 16 in. ft

Enter size and linear feet of timber required on Resources List.



NOTE:
USE THIS CHART WHEN
SUPPORTING BEAM OTHER
THAN TIMBER (STEEL, CONCRETE, ETC.)

TIMBER POST DATA

SECTION 4 • Floors


SECTION 4

FLOORS

INDEX

<u>Page</u>		<u>Page</u>	
	<u>WOOD CONSTRUCTION - FLOOR</u>		<u>CONCRETE CONSTRUCTION - FLOOR</u>
4-1	Timber Joist - Light Design	4-17	Concrete Double Tee - Medium Design
4-2	Glulam - Light Design	4-18	Concrete Waffle Slab - Medium Design
4-3	Timber Joist - Medium Design	4-19	Concrete Flat Slab - Medium Design
4-4	Glulam - Medium Design	4-20	Concrete Flat Plate - Medium Design
4-5	Timber Plank - Heavy Design	4-21	Concrete One-Way Joist - Medium Design
	<u>STEEL - LIGHT CONSTRUCTION - FLOOR</u>	4-22	Concrete Hollow-Core - Medium Design
4-6	Steel Open-Web Joist - Light Design		<u>CONCRETE CONSTRUCTION - FLOOR</u>
4-7	Steel Open-Web Joist - Medium Design	4-23	Concrete Double Tee - Heavy Design
	<u>STEEL - HEAVY CONSTRUCTION - FLOOR</u>	4-24	Concrete Waffle Slab - Heavy Design
4-8	Beam & Slab - Light Design	4-25	Concrete Flat Slab - Heavy Design
4-9	Beam & Slab - Medium Design	4-26	Concrete Flat Plate - Heavy Design
4-10	Beam & Slab - Heavy Design	4-27	Concrete One-Way Joist - Heavy Design
	<u>CONCRETE CONSTRUCTION - FLOOR</u>	4-28	Concrete Hollow-Core - Heavy Design
4-11	Concrete - Double Tee - Light Design		
4-12	Concrete Waffle Slab - Light Design		
4-13	Concrete Flat Slab - Light Design		
4-14	Concrete Flat Plate - Light Design		
4-15	Concrete One-Way Joist - Light Design		
4-16	Concrete Hollow-Core - Light Design		

WOOD CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
TIMBER JOIST-LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40 100 1000	1 1.5 3	VI ⁺ VI 0	Page 6-1	Page 8-1	Page 7-1	
Post and Beam Shores at Mid- span	40 100 1000	1 1.5 3	VI ⁺ VI 0	Page 6-2	Page 8-2, 8-3	Page 7-2	
King Post Truss	40 100 1000	1 1.5 3	VI ⁺ VI ⁺ 0	Page 6-3		Page 7-3	
Flange	40 100 1000	1 1.5 3	VI ⁺ VI ⁻ +	Page 6-4		Page 7-4	
Boxed Beam	40 100 1000	1 1.5 3	VI VI ⁻ +	Page 6-5		Page 7-5	



TYPICALLY FOUND IN RESIDENTIAL BASEMENTS AND SMALL COMMERCIAL BUILDINGS.

SPANS NORMALLY 6 FT TO 18 FT, DEPTH OF JOIST 6 IN. TO 12 IN. SUPPORT BEAM CAN BE EITHER STEEL OR WOOD, AND SUPPORT POSTS WOOD OR STEEL PIPE. DESIGN CRITERION 40 - 60 PSF.

RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	0
100	1.5	+
1000	-	-


WOOD CONSTRUCTION--Floors

TIMBER JOIST--Light Design

4-1

AS BUILT

WOOD CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
GLULAM-LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-6	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-7	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				
King Post Truss	40	1	VI ⁺	Page 6-8		Page 7-3	
	100	1.5	VI ⁺				
	1000	3	0				



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.

SPANS NORMALLY 6 FT. TO
18 FT., DEPTH OF GLULAM
JOIST 4 IN. TO 8 IN.,
SUPPORTED ON GLULAM BEAM,
NORMALLY 8 IN. TO 16 IN.
DEEP.

SUPPORT POSTS WOOD OR STEEL
PIPE.

DESIGN CRITERION 40 - 60 PSF


RADIATION		SURVIVAL
PF	KEY	RATING
40	1	0
100	1.5	+
1000	-	-

WOOD CONSTRUCTION--Floors

GLULAM -- Light Design

AS BUILT

WOOD CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
TIMBER JOIST-MEDIUM DESIGN				SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-1	Page 8-1	Page 7-1
	100	1.5	VI			
	1000	3	0			
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-2	Page 8-2, 8-3	Page 7-2
	100	1.5	VI			
	1000	3	0			
King Post Truss	40	1	VI ⁺	Page 6-3		Page 7-3
	100	1.5	VI ⁺			
	1000	3	VI ⁺			
F'ange	40	1	VI ⁺	Page 6-4		Page 7-4
	100	1.5	VI ⁺			
	1000	3	VI ⁺			
Boxed Beam	40	1	VI ⁺	Page 6-5		Page 7-5
	100	1.5	VI ⁺			
	1000	3	VI ⁺			



TYPICALLY FOUND IN RETAIL STORES
AND LIGHT MANUFACTURING BUILDINGS.
SPANS NORMALLY 6 FT TO 18 FT,
DEPTH OF JOIST 6 IN. TO 12 IN.
SUPPORT BEAM CAN BE EITHER STEEL
OR WOOD, AND SUPPORT POSTS, WOOD
OR STEEL PIPE.
DESIGN CRITERION 80 TO 125 PSF


RADIATION		SURVIVAL RATING
PF	KEY	
40	1	VI-
100	1.5	0
1000	3	+

WOOD CONSTRUCTION—Floors

TIMBER JOIST—Medium Design

AS BUILT

WOOD CONSTRUCTION - FLOOR					SURVIVAL RATING VI	
GLULAM-MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD -80 to 125 PSF	
SUPPORT SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40 100 1000	1 1.5 3	VI ⁺ VI 0	Page 6-6	Page 8-1	Page 7-1
Post and Beam Shores at Mid- span	40 100 1000	1 1.5 3	VI ⁺ VI 0	Page 6-7	Page 8-2, 8-3	Page 7-2
King Post Truss	40 100 1000	1 1.5 3	VI ⁺ VI ⁺ VI ⁺	Page 6-8		Page 7-3



TYPICALLY FOUND IN RETAIL STORES AND LIGHT MANUFACTURING BUILDINGS.

SPANS NORMALLY 6 FT TO 18 FT, DEPTH OF GLULAM JOIST, 6 IN. TO 8 IN., SUPPORTED ON GLULAM BEAM, NORMALLY 8 IN. TO 16 IN. DEEP.

SUPPORT POSTS WOOD OR STEEL PIPE.

DESIGN CRITERION 80 - 125 PSF.


RADIATION		SURVIVAL RATING
P _F	KEY	
40	1	VI-
100	1.5	0
1000	-	+

WOOD CONSTRUCTION—Floors

GLULAM — Medium Design

AS BUILT

WOOD CONSTRUCTION - FLOOR					SURVIVAL RATING VI	
TIMBER PLANK-HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD 150 to 250 PSF	
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
None Required	40	1	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>		
	100	1.5	VI ⁺			
	1000	3	VI ⁺			



TYPICALLY FOUND IN HEAVY MANUFACTURING BUILDINGS AND STORAGE WAREHOUSES.

SPANS NORMALLY 6 FT TO 18 FT.
BEAM MINIMUM 4 IN. BY 4 IN. SIZE,
GIRDERS MINIMUM 8 IN. BY 8 IN. SIZE.

PLANK FLOOR MINIMUM 3 IN. TIMBER,
COLUMNS USUALLY TIMBER, MINIMUM 8 IN. BY 8 IN.

DESIGN CRITERION 150 - 250 PSF.

RADIATION		SURVIVAL
Pf	KEY	RATING
40	1	VI ⁺
100	1.5	VI ⁺
1000	3	VI ⁺


WOOD CONSTRUCTION—Floors

TIMBER PLANK—Heavy Design

4-5

AS BUILT

STEEL - LIGHT CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
OPEN-WEB JOIST - LIGHT DESIGN				SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-9	Page 8-1	Page 7-1
	100	1.5	VI			
	1000	3	0			
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-10	Page 8-2, 8-3	Page 7-2
	100	1.5	VI			
	1000	3	0			




TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 8 FT TO 26 FT.
OPEN-WEB JOIST DEPTH 8 IN. TO
16 IN.
SUPPORT BEAM NORMALLY STEEL.
DESIGN CRITERION 40 - 60 PSF.

RADIATION		SURVIVAL RATING
PF	KEY	
40	1	0
100	1.5	+
1000	-	-

STEEL-LIGHT CONSTRUCTION-Floors AS BUILT

OPEN-WEB JOIST-Light Design

STEEL - LIGHT CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
OPEN-WEB JOIST - MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-9	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-10	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				
King Post Truss	40	1	VI ⁺	Page 6-11		Page 7-3	
	100	1.5	VI ⁺				
	1000	3	0				



TYPICALLY FOUND IN RETAIL STORES
AND LIGHT MANUFACTURING BUILDINGS,
SPANS NORMALLY 8 FT TO 28 FT,
OPEN-WEB JOIST DEPTH 8 IN. TO
20 IN.
SUPPORT BEAM NORMALLY STEEL,
DESIGN CRITERION 80 - 125 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	0
100	1.5	0
1000	3	+

STEEL-LIGHT CONSTRUCTION-Floors

OPEN-WEB JOIST-Medium Design

AS BUILT

STEEL - HEAVY CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
BEAM AND SLAB-LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-12	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-13	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.

SPANS NORMALLY 6 FT TO
18 FT, DEPTH OF BEAMS
4 IN. TO 8 IN., SUP-
PORTED ON STEEL GIRDER,
NORMALLY 8 IN. TO 12 IN.
DEEP.

SUPPORT COLUMNS NORMALLY
STEEL.

DESIGN CRITERION 40 -
60 PSF.


RADIATION PF	KEY	SURVIVAL PATING
40	1	0
100	1.5	0
1000	3	+

STEEL-HEAVY CONSTRUCTION-Floors

BEAM AND SLAB-Light Design

AS BUILT

STEEL - HEAVY CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
BEAM AND SLAB-MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-12	Page 8-1	Page 7-1	
	100	1	VI				
	1000	2.5	0				
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-13	Page 8-2, 8-3	Page 7-2	
	100	1	VI				
	1000	2.5	0				



TYPICALLY FOUND IN RETAIL STORES AND LIGHT MANUFACTURING BUILDINGS.

SPANS NORMALLY 6 FT TO 20 FT, DEPTH OF BEAMS 6 IN. TO 8 IN., SUPPORTED ON STEEL GIRDER, NORMALLY 8 IN. TO 16 IN. DEEP.

SUPPORT COLUMNS NORMALLY STEEL,

DESIGN CRITERION 80 - 125 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1900	2.5	+

STEEL-HEAVY CONSTRUCTION-Floors

BEAM AND SLAB-Medium Design

AS BUILT

STEEL - HEAVY CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
BEAM AND SLAB-HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD-150 to 250 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
None Required	40	0.5	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>			
	100	1	VI				
	1000	2.5	0				



TYPICALLY FOUND IN HEAVY
MANUFACTURING BUILDINGS
AND STORAGE WAREHOUSES.

SPANS NORMALLY 10 FT TO
24 FT, DEPTH OF BEAMS
8 IN. TO 16 IN., SUP-
PORTED ON STEEL GIRDERS,
NORMALLY 12 IN. TO 24 IN.
DEEP.

SUPPORT COLUMN NORMALLY
STEEL.

DESIGN CRITERION 150 -
250 PSF.


RADIATION		SURVIVAL RATING
PF	KEY	
40	0.5	VI ⁺
100	1	VI
1000	2.5	0

STEEL-HEAVY CONSTRUCTION-Floors

BEAM AND SLAB-Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
DOUBLE TEES- LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-14	Page 8-1	Page 7-1	
	100	1	VI				
	1000	2.5	0				
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-15	Page 8-2, 8-3	Page 7-2	
	100	1	VI				
	1000	2.5	0				




TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 12 FT TO 24 FT
STEMS 6 IN. TO 14 IN. DEEP.
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DESIGN CRITERION 40 TO
60 PSF.

RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION—Floors DOUBLE TEE—Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
WAFFLE SLAB-LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _F	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Post Shores at Midspan	40	0.5	VI ⁺	Page 6-16	Page 8-4	Page 7-6	
	100	1	VI				
	1000	2.5	0				



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS,
SPANS NORMALLY 15 FT TO
36 FT,
RIBS 8 IN. TO 12 IN.
DEEP,
CONCRETE COLUMNS.
DESIGN CRITERION 40 TO
60 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION—Floors

WAFFLE SLAB—Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
FLAT SLAB - LIGHT DESIGN				SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P_f	KEY	S_R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	N	VI^+	Page 6-17	Page 8-4	Page 7-6
	100	0.5	VI^+			
	1000	2	0			



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 15 FT
TO 24 FT.
SLAB 6 IN. TO 10 IN.
THICK.
CONCRETE COLUMNS.
DESIGN CRITERION 40 TO
60 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	N	0
100	0.5	0
1000	2	0

CONCRETE CONSTRUCTION—Floors

FLAT SLAB — Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
FLAT PLATE - LIGHT DESIGN				SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	N	VI ⁺	Page 6-18	Page 8-1	Page 7-6
	100	0.5	VI ⁺			
	1000	2	0			



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 12 FT
TO 26 FT.
SLAB 5 IN. TO 10 IN.
THICK.
CONCRETE COLUMNS.
DESIGN CRITERION 40 -
60 PSF.


PADIATION		SURVIVAL
PF	KEY	RATING
40	N	0
100	0.5	0
1000	2	0

CONCRETE CONSTRUCTION-Floors

FLAT PLATE - Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
ONE-WAY JOIST - LIGHT DESIGN					SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-19	Page 8-1	Page 7-1	
	100	1	VI				
	1000	2.5	0				
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-20	Page 8-2, 8-3	Page 7-2	
	100	1	VI				
	1000	2.5	0				



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 14 FT TO
26 FT.
RIBS 8 IN. TO 12 IN. DEEP,
CONCRETE COLUMNS.
DESIGN CRITERION 40 -
60 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION-Floors

ONE-WAY JOIST - Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
HOLLOW-CORE - LIGHT DESIGN				SUPERIMPOSED DESIGN LOAD-40 to 60 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-21	Page 8-1	Page 7-1
	100	1	VI			
	1000	2.5	0			
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-22	Page 8-2, 8-3	Page 7-2
	100	1	VI			
	1000	2.5	0			



TYPICALLY FOUND IN SMALL
COMMERCIAL BUILDINGS.
SPANS NORMALLY 12 FT TO
34 FT.
SLAB 4 IN. TO 8 IN. THICK,
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DESIGN CRITERION 40 TO
60 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION—Floors

HOLLOW-CORE — Light Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
DOUBLE TEES - MEDIUM DESIGN				SUPERIMPOSED DESIGN LOAD- 80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-14	Page 8-1	Page 7-1
	100	1	VI			
	1000	2:5	0			
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-15	Page 8-2, 8-3	Page 7-2
	100	1	VI			
	1000	2.5	0			



TYPICALLY FOUND IN RETAIL STORES AND LIGHT MANUFACTURING BUILDINGS.

SPANS NORMALLY 18 FT TO 30 FT.

STEMS 12 IN. TO 18 IN. DEEP.

SUPPORT BEAMS AND COLUMNS USUALLY CONCRETE.


DESIGN CRITERION 80 TO 125 PSF.

RADIATION		SURVIVAL
Pf	KEY	RATING
40	0.5	0
100	1	0
1000	2.5	0

CONCRETE CONSTRUCTION--Floors DOUBLE TEE - Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
WAFFLE SLAB-MEDIUM DESIGN				SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	0.5	VI ⁺	Page 6-16	Page 8-4	Page 7-6
	100	1	VI			
	1000	2.5	0			



TYPICALLY FOUND IN RETAIL
STORES AND LIGHT MANUFAC-
TURING BUILDINGS.

SPANS NORMALLY 15 FT TO
36 FT.

RIBS 10 IN. TO 14 IN.
DEEP.

CONCRETE COLUMNS,
DESIGN CRITERION 80 TO
125 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	0

CONCRETE CONSTRUCTION-Floors

WAFFLE SLAB - Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
FLAT SLAB - MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _F	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Post Shores at Midspan	40	N	VI ⁺	Page 6-17	Page 8-4	Page 7-6	
	100	0.5	VI				
	1000	2	0				



TYPICALLY FOUND IN
RETAIL STORES AND LIGHT
MANUFACTURING BUILDINGS.
SPANS NORMALLY 18 FT
TO 30 FT.
SLAB 8 IN. TO 10 IN.
THICK.
CONCRETE COLUMNS,
DESIGN CRITERION 80 -
125 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	N	VI
100	0.5	0
1000	2	0

CONCRETE CONSTRUCTION-Floors

FLAT SLAB - Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
FLAT PLATE - MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Post Shores at Midspan	40	N	VI ⁺	Page 6-18	Page 8-4	Page 7-6	
	100	0.5	VI				
	1000	2	0				



TYPICALLY FOUND IN RE-
TAIL STORES AND LIGHT
MANUFACTURING BUILDINGS.
SPANS NORMALLY 16 FT
TO 26 FT.
SLAB 6 IN. TO 10 IN.
THICK.
CONCRETE COLUMNS.
DESIGN CRITERION 80 -
125 PSF.


PADIATION		SURVIVAL
Pf	KEY	RATING
40	N	VI
100	0.5	0
1000	2	0

CONCRETE CONSTRUCTION-Floors

FLAT PLATE - Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
ONE-WAY JOIST - MEDIUM DESIGN				SUPERIMPOSED DESIGN LOAD-80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-19	Page 8-1	Page 7-1
	100	1	VI			
	1000	2:5	0			
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-20	Page 8-2, 8-3	Page 7-2
	100	1	VI			
	1000	2.5	0			



TYPICALLY FOUND IN RETAIL
STORES AND LIGHT MANUFACTURING
BUILDINGS.

SPANS NORMALLY 16 FT TO
28 FT.

RIBS 10 IN. TO 14 IN.
DEEP.

CONCRETE COLUMNS.

DESIGN CRITERION 80 TO
125 PSF.


PADIATION		SURVIVAL
Pf	KEY	RATING
40	0.5	0
100	1	0
1000	2.5	0

CONCRETE CONSTRUCTION-Floors

ONE-WAY JOIST- Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
HOLLOW-CORE - MEDIUM DESIGN					SUPERIMPOSED DESIGN LOAD- 80 to 125 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS- Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	0.5	VI ⁺	Page 6-21	Page 8-1	Page 7-1	
	100	1	VI				
	1000	2:5	0				
Post and Beam Shores at Mid- span	40	0.5	VI ⁺	Page 6-22	Page 8-2, 8-3	Page 7-2	
	100	1	VI				
	1000	2.5	0				



TYPICALLY FOUND IN RETAIL
STORES AND LIGHT MANUFACTURING
BUILDINGS.
SPANS NORMALLY 16 FT TO
30 FT.
SLAB 6 IN. TO 10 IN. THICK.
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DESIGN CRITERION 80 TO
125 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	0

CONCRETE CONSTRUCTION—Floors

HOLLOW-CORE — Medium Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
DOUBLE TEES - HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD-150 to 250 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
None Required	40	0.5	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>			
	100	1	VI ⁺				
	1000	2.5	VI				



TYPICALLY FOUND IN HEAVY
MANUFACTURING BUILDINGS
AND STORAGE WAREHOUSES.
SPANS NORMALLY 18 FT TO
30 FT.
STEMS 16 IN. TO 32 IN. DEEP.
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DESIGN CRITERION 150 TO
250 PSF.


RADIATION		SURVIVAL
Pf	KEY	RATING
40	0.5	VI ⁺
100	1	VI ⁺
1000	2.5	VI

CONCRETE CONSTRUCTION--Floors

DOUBLE TEE - Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
WAFFLE SLABS - HEAVY DESIGN				SUPERIMPOSED DESIGN LOAD-150 to 250 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
None Required	40	0.5	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>		
	100	1	VI ⁺			
	1000	2.5	VI			



TYPICALLY FOUND IN HEAVY
MANUFACTURING BUILDINGS
AND STORAGE WAREHOUSES.
SPANS NORMALLY 15 FT TO
36 FT.
RIBS 10 IN. TO 16 IN. DEEP.
CONCRETE COLUMNS.
DESIGN CRITERION 150 TO
250 PSF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	VI ⁺
100	1	VI ⁺
1000	2.5	VI

CONCRETE CONSTRUCTION—Floors

WAFFLE SLAB—Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI		
FLAT SLAB - HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD-150 to 250 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
None Required	40	N	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>			
	100	0.5	VI ⁺				
	1000	2	VI				



TYPICALLY FOUND IN
HEAVY MANUFACTURING
BUILDINGS AND STORAGE
WAREHOUSES.

SPANS NORMALLY 20 FT
TO 30 FT.

SLAB 8 IN. TO 12 IN.
THICK.

CONCRETE COLUMNS.
DESIGN CRITERION 150
TO 250 PSF.


RADIATION		SURVIVAL
PF	KEY	RATING
40	N	VI ⁺
100	0.5	VI ⁺
1000	2	VI

CONCRETE CONSTRUCTION—Floors

FLAT SLAB — Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR				SURVIVAL RATING VI		
FLAT PLATE - HEAVY DESIGN				SUPERIMPOSED DESIGN LOAD-150 to 250 PSF		
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
None Required	40	N	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>		
	100	0.5	VI ⁺			
	1000	2	VI			




TYPICALLY FOUND IN
HEAVY MANUFACTURING
BUILDINGS AND STORAGE
WAREHOUSES,
SPANS NORMALLY 16 FT
TO 26 FT.
SLAB 8 IN. TO 10 IN.
THICK.
CONCRETE COLUMNS,
DESIGN CRITERION 150
TO 250 PSF.

RADIATION		SURVIVAL RATING
PF	KEY	
40	N	VI ⁺
100	0.5	VI ⁺
1000	2	VI

CONCRETE CONSTRUCTION—Floors FLAT PLATE — Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI	
ONE-WAY JOIST - HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD-150 to 250 PSF	
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
None Required	40	0.5	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>		
	100	1	VI ⁺			
	1000	2.5	VI			



TYPICALLY FOUND IN
HEAVY MANUFACTURING
BUILDINGS AND STORAGE
WAREHOUSES.

SPANS NORMALLY 16 FT
TO 24 FT.

RIBS 10 IN. TO 16 IN.
DEEP.

CONCRETE COLUMNS.

DESIGN CRITERION 150
TO 250 PSF.


RADIATION		SURVIVAL
PF	KEY	RATING
40	0.5	VI ⁺
100	1	VI ⁺
1000	2.5	VI

CONCRETE CONSTRUCTION—Floors

ONE-WAY JOIST—Heavy Design

AS BUILT

CONCRETE CONSTRUCTION - FLOOR					SURVIVAL RATING VI	
HOLLOW - CORE - HEAVY DESIGN					SUPERIMPOSED DESIGN LOAD-150 to 250 PSF	
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
None Required	40	0.5	VI ⁺	<u>DOES NOT REQUIRE UPGRADING</u>		
	100	1	VI ⁺			
	1000	2.5	VI			



TYPICALLY FOUND IN HEAVY
MANUFACTURING BUILDINGS
AND STORAGE WAREHOUSES,
SPANS NORMALLY 18 FT TO
28 FT.
SLAB 8 IN. TO 10 IN.
THICK.
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DESIGN CRITERION 150 TO
250 PSF.

RADIATION		SURVIVAL RATING
PF	KEY	
40	0.5	VI ⁺
100	1	VI ⁺
1000	2.5	VI

CONCRETE CONSTRUCTION--Floors HOLLOW-CORE - Heavy Design

4-28

AS BUILT

SECTION 5 - Roofs

SECTION 5

ROOFS

INDEX

Page

WOOD CONSTRUCTION - ROOFS

Timber Joist
Glulam

5-1
5-2

STEEL-LIGHT CONSTRUCTION - ROOFS

Open-Web Joist w/Timber Deck,
Insulation

5-3

STEEL-HEAVY CONSTRUCTION - ROOFS

Open-Web Joist w/Metal Deck,
Insulation


5-4

CONCRETE CONSTRUCTION - ROOFS

Double Tee
Waffle Slab
Flat Slab
Flat Plate
One-Way Joist
Hollow-Core

5-5
5-6
5-7
5-8
5-9
5-10

WOOD CONSTRUCTION - ROOFS					SURVIVAL RATING VI		
TIMBER JOIST							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Two rows of Wood Stud Walls, one each at 1/3 span	40	1	VI ⁺	Page 6-23	Page 8-1	Page 7-1	
	100	1.5	VI ⁺				
	1000	3	VI ⁺				
Two rows of Post and Beam Shores, one each at 1/3 span	40	1	VI ⁺	Page 6-24	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI ⁺				
	1000	3	VI ⁺				



SPANS NORMALLY 6 FT. TO 24 FT.,
 DEPTH OF JOIST 6 IN. TO 12 IN.,
 SUPPORTED BEAM CAN BE EITHER
 STEEL OR WOOD, AND SUPPORT POSTS
 WOOD OR STEEL PIPE.
 DECK TOPPED WITH PLYWOOD, IN-
 SULATION, AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	+
100	-	-
1000	-	-

WOOD CONSTRUCTION-ROOFS

TIMBER JOIST

AS BUILT

WOOD CONSTRUCTION - ROOFS					SURVIVAL RATING VI		
GLULAM							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Two rows of Wood Stud Walls, one each at 1/3 span	40	1	VI ⁺	Page 6-25	Page 8-1	Page 7-1	
	100	1.5	VI ⁺				
	1000	3	VI ⁺				
Two rows of Post and Beam Shores, one each at 1/3 span	40	1	VI ⁺	Page 6-26	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI ⁺				
	1000	3	VI ⁺				

AD-A085 024


SCIENTIFIC SERVICE INC REDWOOD CITY CA
SHELTER UPGRADING MANUAL: HOST AREA SHELTERS. (U)
MAR 80 C WILTON, B L GABRIELSEN, R S TANSLEY
SSI-7815-8


F/6 13/13


UNCLASSIFIED

DCPA01-78-C-0215
NL

2 of 3
AD-A
340 024







SPANS NORMALLY 6 FT. TO 24 FT., DEPTH OF GLULAM JOIST 4 IN. TO 8 IN., SUPPORTED ON GLULAM BEAM, NORMALLY 8 IN. TO 16 IN. DEEP.

SUPPORT POSTS WOOD OR STEEL PIPE.

DECK TOPPED WITH PLYWOOD, INSULATION AND BUILT-UP ROOF.


RADIATION		SURVIVAL RATING
P _F	KEY	
40	1	+
100	-	-
1000	-	-

WOOD CONSTRUCTION—Roofs

GLULAM

AS BUILT

STEEL - LIGHT CONSTRUCTION - ROOFS					SURVIVAL RATING VI		
OPEN-WEB JOIST W/TIMBER DECK, INSULATION							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Two rows of Wood Stud Walls, one each at 1/3 span	40	1	VI ⁺	Page 6-27	Page 8-1	Page 7-1	
	100	1.5	VI ⁻				
	1000	3	0				
Two rows of Post and Beam Shores, one each at 1/3 span	40	1	VI ⁺	Page 6-28	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI ⁻				
	1000	3	0				



SPANS NORMALLY 8 FT TO 24 FT.
OPEN-WEB JOIST DEPTH 8 IN.
TO 12 IN.


SUPPORT BEAM: NORMALLY STEEL.
DECK TOPPED WITH PLYWOOD,
INSULATION, AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
PF	KEY	
40	1	+
100	-	-
1000	-	-

STEEL LIGHT CONSTRUCTION--Roofs
OPEN-WEB JOIST

AS BUILT

STEEL - HEAVY CONSTRUCTION - ROOFS					SURVIVAL RATING VI		
OPEN-WEB JOIST W/METAL DECK, INSULATION							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Two rows of Wood Stud Walls, one each at 1/3 span	40	1	VI ⁺	Page 6-29	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Two rows of Post and Beam Shores, one each at 1/3 span	40	1	VI ⁺	Page 6-30	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				



SPANS NORMALLY 16 FT TO 30 FT.
OPEN-WEB JOIST DEPTH 8 IN. TO
16 IN.

SUPPORT BEAM NORMALLY STEEL.
DECK TOPPED WITH METAL DECK,
INSULATION, AND BUILT-UP ROOF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	+
100	-	-
1000	-	-

STEEL HEAVY CONSTRUCTION-ROOFS

OPEN-WEB JOIST

AS BUILT

CONCRETE CONSTRUCTION - ROOFS						SURVIVAL RATING VI	
DOUBLE TEES							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-31	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-32	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				




SPANS NORMALLY 16 FT TO 40 FT.
STEMS 8 IN. TO 24 IN. DEEP,
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	0
100	1.5	+
1000	-	-

CONCRETE CONSTRUCTION-ROOFS DOUBLE TEE

AS BUILT

CONCRETE CONSTRUCTION - ROOFS					SURVIVAL RATING VI	
WAFFLE SLAB						
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	1	VI ⁺	Page 6-33	Page 8-4	Page 7-6
	100	1.5	VI			
	1000	3	0			




SPANS NORMALLY 16 FT TO 30 FT.
RIBS 6 IN. TO 10 IN. DEEP.
CONCRETE COLUMNS.
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	0
100	1.5	+
1000	-	-

CONCRETE CONSTRUCTION—Roofs WAFFLE SLAB

AS BUILT

CONCRETE CONSTRUCTION - ROOFS					SURVIVAL RATING VI	
FLAT SLAB						
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	0.5	VI ⁺	Page 6-34	Page 8-4	Page 7-6
	100	1	VI			
	1000	2.5	0			



SPANS NORMALLY 16 FT TO 30 FT,
SLAB 6 IN. TO 10 IN. THICK,
CONCRETE COLUMNS,
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION--Roofs

FLAT SLAB

AS BUILT

CONCRETE CONSTRUCTION - ROOFS					SURVIVAL RATING VI	
FLAT PLATE						
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Post Shores at Midspan	40	0.5	VI ⁺	Page 6-35	Page 8-4	Page 7-6
	100	1	VI			
	1000	2.5	0			




SPANS NORMALLY 16 FT TO 30 FT.
SLAB 6 IN. TO 10 IN.
CONCRETE COLUMNS.
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
PF	KEY	
40	0.5	0
100	1	0
1000	2.5	+

CONCRETE CONSTRUCTION—Roofs FLAT PLATE

AS BUILT

CONCRETE CONSTRUCTION - ROOFS						SURVIVAL RATING VI	
ONE-WAY JOIST							
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7	
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-36	Page 8-1	Page 7-1	
	100	1.5	VI				
	1000	3	0				
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-37	Page 8-2, 8-3	Page 7-2	
	100	1.5	VI				
	1000	3	0				



SPANS NORMALLY 16 FT TO 35 FT.
RIBS 8 IN. TO 14 IN. DEEP
CONCRETE COLUMNS,
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.


RADIATION		SURVIVAL RATING
Pf	KEY	
40	1	0
100	1.5	+
1000	-	-

CONCRETE CONSTRUCTION—Roofs

ONE-WAY JOIST

AS BUILT

CONCRETE CONSTRUCTION - ROOFS					SURVIVAL RATING VI	
HOLLOW-CORE						
SHORING SYSTEM REQUIRED	P _f	KEY	S _R	ILLUSTRATION AND DETAILS-Sect. 6	CHARTS FOR SIZE AND SPACING OF SHORES Sect. 8	WORKSHEETS Sect. 7
Wood Stud Wall at Midspan	40	1	VI ⁺	Page 6-38	Page 8-1	Page 7-1
	100	1.5	VI			
	1000	3	0			
Post and Beam Shores at Mid- span	40	1	VI ⁺	Page 6-39	Page 8-2, 8-3	Page 7-2
	100	1.5	VI			
	1000	3	0			



SPANS NORMALLY 15 FT TO 40 FT.
SLAB 4 IN. TO 10 IN. THICK.
SUPPORT BEAMS AND COLUMNS
USUALLY CONCRETE.
DECK TOPPED WITH INSULATION
AND BUILT-UP ROOF.

RADIATION		SURVIVAL RATING
P _F	KEY	
40	1	0
100	1.5	+
1000	-	-

CONCRETE CONSTRUCTION—ROOFS

HOLLOW—CORE

AS BUILT

SECTION 6 - Illustrations

SECTION 6

ILLUSTRATIONS

INDEX







<u>Page</u>		<u>Page</u>	
	<u>WOOD CONSTRUCTION - FLOORS</u>		<u>CONCRETE CONSTRUCTION - FLOORS</u>
6-1	Timber Joist - Stud Wall Upgrading	6-21	Hollow-Core - Stud Wall Upgrading
6-2	- Post & Beam Upgrading	6-22	- Post & Beam Upgrading
6-3	- King Post Truss Upgrading		<u>WOOD CONSTRUCTION - ROOFS</u>
6-4	- Flange Upgrading	6-23	Timber Joist - Stud Wall Upgrading
6-5	- Boxed Beam Upgrading	6-24	- Post & Beam Upgrading
6-6	Glulam - Stud Wall Upgrading	6-25	Glulam - Stud Wall Upgrading
6-7	- Post & Beam Upgrading	6-26	- Post & Beam Upgrading
6-8	- King Post Truss Upgrading		<u>STEEL LIGHT CONSTRUCTION - ROOFS</u>
	<u>STEEL - LIGHT CONSTRUCTION - FLOORS</u>	6-27	Open-Web Joist - Stud Wall Upgrading
6-9	Open-Web Joist - Stud Wall Upgrading	6-28	- Post & Beam Upgrading
6-10	- Post & Beam Upgrading		<u>STEEL HEAVY CONSTRUCTION - ROOFS</u>
6-11	- King Post Truss Upgrading	6-29	Open-Web Joist - Stud Wall Upgrading
	<u>STEEL - HEAVY CONSTRUCTION - FLOORS</u>	6-30	- Post & Beam Upgrading
6-12	Beam and Slab - Stud Wall Upgrading		<u>CONCRETE CONSTRUCTION - ROOFS</u>
6-13	- Post & Beam Upgrading	6-31	Double Tee - Stud Wall Upgrading
	<u>CONCRETE CONSTRUCTION - FLOORS</u>	6-32	- Post & Beam Upgrading
6-14	Double Tee - Stud Wall Upgrading	6-33	Waffle Slab - Post Upgrading
6-15	- Post & Beam Upgrading	6-34	Flat Slab - Post Upgrading
6-16	Waffle Slab - Post Upgrading	6-35	Flat Plate - Post Upgrading
6-17	Flat Slab - Post Upgrading	6-36	One-Way Joist - Stud Wall Upgrading
6-18	Flat Plate - Post Upgrading	6-37	- Post & Beam Upgrading
6-19	One-Way Joist - Stud Wall Upgrading	6-38	Hollow-Core - Stud Wall Upgrading
6-20	- Post & Beam Upgrading	6-39	- Post & Beam Upgrading

STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)	_____	_____
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)	_____	_____
3. Nails	_____	_____
4. Hammer	_____	_____
5. Saw	_____	_____
6. Wedges	_____	_____
7. Tape measure/yardstick, etc.	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____

details



BOARD SIZE (MINIMUM)	NAIL SIZE
1 x 10	6d, 8d
2 x 10	8d, 10d, 12d
3 x 10	10d, 20d, 30d
4 x 10	40d, 50d, 60d

a. where b = width of board
 where b = 2 in. or less
 where b = 4 in. or less
 where b = 6 in. or less
 where b = 8 in. or less
 where b = 10 in. or less

WOOD CONSTRUCTION—Floors TIMBER JOIST



stud wall upgrading

POST & BEAM

RESOURCE LIST


<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		

details



NAILING	CRITICAL	TAIL SIZE
BOARD SIZE (IN NOMINAL)		
1 x 10	6d	8d
2 x 10	8d	10d 12d
3 x 10	10d	20d 30d
4 x 10	40d	50d 60d

a where b = width of board
 when b = 2 in. use 2 nails
 when b = 4 in. use 4 nails
 when b = 6 in. use 6 nails



WOOD CONSTRUCTION—Floors

TIMBER JOIST

post & beam upgrading



KING POST TRUSS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber	_____	_____
2. Cable or Rods	_____	_____
3. Connections	_____	_____
4. Nails	_____	_____
5. Hammer	_____	_____
6. Saw	_____	_____
7. Wedges	_____	_____
8. Tape measure/yardstick, etc.	_____	_____
9. _____	_____	_____
10. _____	_____	_____

king post truss upgrading

details





BOARD SIZE IN INCHES	NAILING - OFF	NAUL SIZE
1 x 2	6d	16
2 x 2	8d	16
2 x 4	10d	16
2 x 6	12d	16
2 x 8	14d	16
2 x 10	16d	16
2 x 12	18d	16
4 x 4	20d	16
4 x 6	22d	16
4 x 8	24d	16
4 x 10	26d	16
4 x 12	28d	16
6 x 6	30d	16
6 x 8	32d	16
6 x 10	34d	16
6 x 12	36d	16
8 x 8	38d	16
8 x 10	40d	16
8 x 12	42d	16
10 x 10	44d	16
10 x 12	46d	16
12 x 12	48d	16

FLANGE

RESOURCE LIST


<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber		
2. Glue		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		

details



BOARD SIZE (MINIMUM)	NAIL SIZE
1 x 6	6d, 8d
2 x 6	8d, 10d, 12d
3 x 6	10d, 20d, 30d
4 x 6	40d, 50d, 60d



* where 6" is width of joists
when 1" = 2" in use 4 nails
when 1" = 4" in use 5 nails
when 1" = 6" in use 6 nails



WOOD CONSTRUCTION—Floors

TIMBER JOIST

flange upgrading



WOOD CONSTRUCTION—Floors

boxed beam upgrading

STUD WALL

RESOURCE LIST

Required

1. Timber (Studs & Plates)
2. Bracing Material
(Plywood Sheeting or
nom. 1-in. Timber)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
8. _____
9. _____
10. _____

Quantity







Available

WOOD CONSTRUCTION—FLOORS
GLULAM

stud wall upgrading

6-9



details



BOAT'S NAME	NAUTICAL CODE	NAME	AGE
1	X	W	2
2	X	W	2
3	X	W	3
4	X	W	4
5	X	W	5
6	X	W	6
7	X	W	7
8	X	W	8
9	X	W	9
10	X	W	10
11	X	W	11
12	X	W	12
13	X	W	13
14	X	W	14
15	X	W	15
16	X	W	16
17	X	W	17
18	X	W	18
19	X	W	19
20	X	W	20
21	X	W	21
22	X	W	22
23	X	W	23
24	X	W	24
25	X	W	25
26	X	W	26
27	X	W	27
28	X	W	28
29	X	W	29
30	X	W	30
31	X	W	31
32	X	W	32
33	X	W	33
34	X	W	34
35	X	W	35
36	X	W	36
37	X	W	37
38	X	W	38
39	X	W	39
40	X	W	40
41	X	W	41
42	X	W	42
43	X	W	43
44	X	W	44
45	X	W	45
46	X	W	46
47	X	W	47
48	X	W	48
49	X	W	49
50	X	W	50
51	X	W	51
52	X	W	52
53	X	W	53
54	X	W	54
55	X	W	55
56	X	W	56
57	X	W	57
58	X	W	58
59	X	W	59
60	X	W	60
61	X	W	61
62	X	W	62
63	X	W	63
64	X	W	64
65	X	W	65
66	X	W	66
67	X	W	67
68	X	W	68
69	X	W	69
70	X	W	70
71	X	W	71
72	X	W	72
73	X	W	73
74	X	W	74
75	X	W	75
76	X	W	76
77	X	W	77
78	X	W	78
79	X	W	79
80	X	W	80
81	X	W	81
82	X	W	82
83	X	W	83
84	X	W	84
85	X	W	85
86	X	W	86
87	X	W	87
88	X	W	88
89	X	W	89
90	X	W	90
91	X	W	91
92	X	W	92
93	X	W	93
94	X	W	94
95	X	W	95
96	X	W	96
97	X	W	97
98	X	W	98
99	X	W	99
100	X	W	100

= where b = width of bar, t = thickness of bar, E = modulus of elasticity, P = load, L = length of bar, δ = deflection.

details





NAILING SCHEDULE	
BOARD SIZE (MINIMUM)	NAIL SIZE
1 x 10	6d
2 x 10	8d
3 x 10	10d
4 x 10	12d
5 x 10	14d
6 x 10	16d
8 x 10	18d
10 x 10	20d
12 x 10	22d
14 x 10	24d
16 x 10	26d
18 x 10	28d
20 x 10	30d
22 x 10	32d
24 x 10	34d
26 x 10	36d
28 x 10	38d
30 x 10	40d
32 x 10	42d
34 x 10	44d
36 x 10	46d
38 x 10	48d
40 x 10	50d
42 x 10	52d
44 x 10	54d
46 x 10	56d
48 x 10	58d
50 x 10	60d
52 x 10	62d
54 x 10	64d
56 x 10	66d
58 x 10	68d
60 x 10	70d
62 x 10	72d
64 x 10	74d
66 x 10	76d
68 x 10	78d
70 x 10	80d
72 x 10	82d
74 x 10	84d
76 x 10	86d
78 x 10	88d
80 x 10	90d
82 x 10	92d
84 x 10	94d
86 x 10	96d
88 x 10	98d
90 x 10	100d
92 x 10	102d
94 x 10	104d
96 x 10	106d
98 x 10	108d
100 x 10	110d
102 x 10	112d
104 x 10	114d
106 x 10	116d
108 x 10	118d
110 x 10	120d
112 x 10	122d
114 x 10	124d
116 x 10	126d
118 x 10	128d
120 x 10	130d
122 x 10	132d
124 x 10	134d
126 x 10	136d
128 x 10	138d
130 x 10	140d
132 x 10	142d
134 x 10	144d
136 x 10	146d
138 x 10	148d
140 x 10	150d
142 x 10	152d
144 x 10	154d
146 x 10	156d
148 x 10	158d
150 x 10	160d
152 x 10	162d
154 x 10	164d
156 x 10	166d
158 x 10	168d
160 x 10	170d
162 x 10	172d
164 x 10	174d
166 x 10	176d
168 x 10	178d
170 x 10	180d
172 x 10	182d
174 x 10	184d
176 x 10	186d
178 x 10	188d
180 x 10	190d
182 x 10	192d
184 x 10	194d
186 x 10	196d
188 x 10	198d
190 x 10	200d
192 x 10	202d
194 x 10	204d
196 x 10	206d
198 x 10	208d
200 x 10	210d
202 x 10	212d
204 x 10	214d
206 x 10	216d
208 x 10	218d
210 x 10	220d
212 x 10	222d
214 x 10	224d
216 x 10	226d
218 x 10	228d
220 x 10	230d
222 x 10	232d
224 x 10	234d
226 x 10	236d
228 x 10	238d
230 x 10	240d
232 x 10	242d
234 x 10	244d
236 x 10	246d
238 x 10	248d
240 x 10	250d
242 x 10	252d
244 x 10	254d
246 x 10	256d
248 x 10	258d
250 x 10	260d
252 x 10	262d
254 x 10	264d
256 x 10	266d
258 x 10	268d
260 x 10	270d
262 x 10	272d
264 x 10	274d
266 x 10	276d
268 x 10	278d
270 x 10	280d
272 x 10	282d
274 x 10	284d
276 x 10	286d
278 x 10	288d
280 x 10	290d
282 x 10	292d
284 x 10	294d
286 x 10	296d
288 x 10	298d
290 x 10	300d
292 x 10	302d
294 x 10	304d
296 x 10	306d
298 x 10	308d
300 x 10	310d
302 x 10	312d
304 x 10	314d
306 x 10	316d
308 x 10	318d
310 x 10	320d
312 x 10	322d
314 x 10	324d
316 x 10	326d
318 x 10	328d
320 x 10	330d
322 x 10	332d
324 x 10	334d
326 x 10	336d
328 x 10	338d
330 x 10	340d
332 x 10	342d
334 x 10	344d
336 x 10	346d
338 x 10	348d
340 x 10	350d
342 x 10	352d
344 x 10	354d
346 x 10	356d
348 x 10	358d
350 x 10	360d
352 x 10	362d
354 x 10	364d
356 x 10	366d
358 x 10	368d
360 x 10	370d
362 x 10	372d
364 x 10	374d
366 x 10	376d
368 x 10	378d
370 x 10	380d
372 x 10	382d
374 x 10	384d
376 x 10	386d
378 x 10	388d
380 x 10	390d
382 x 10	392d
384 x 10	394d
386 x 10	396d
388 x 10	398d
390 x 10	400d
392 x 10	402d
394 x 10	404d
396 x 10	406d
398 x 10	408d
400 x 10	410d
402 x 10	412d
404 x 10	414d
406 x 10	416d
408 x 10	418d
410 x 10	420d
412 x 10	422d
414 x 10	424d
416 x 10	426d
418 x 10	428d
420 x 10	430d
422 x 10	432d
424 x 10	434d
426 x 10	436d
428 x 10	438d
430 x 10	440d
432 x 10	442d
434 x 10	444d
436 x 10	446d
438 x 10	448d
440 x 10	450d
442 x 10	452d
444 x 10	454d
446 x 10	456d
448 x 10	458d
450 x 10	460d
452 x 10	462d
454 x 10	464d
456 x 10	466d
458 x 10	468d
460 x 10	470d
462 x 10	472d
464 x 10	474d
466 x 10	476d
468 x 10	478d
470 x 10	480d
472 x 10	482d
474 x 10	484d
476 x 10	486d
478 x 10	488d
480 x 10	490d
482 x 10	492d
484 x 10	494d
486 x 10	496d
488 x 10	498d
490 x 10	500d
492 x 10	502d
494 x 10	504d
496 x 10	506d
498 x 10	508d
500 x 10	510d
502 x 10	512d
504 x 10	514d
506 x 10	516d
508 x 10	518d
510 x 10	520d
512 x 10	522d
514 x 10	524d
516 x 10	526d
518 x 10	528d
520 x 10	530d
522 x 10	532d
524 x 10	534d
526 x 10	536d
528 x 10	538d
530 x 10	540d
532 x 10	542d
534 x 10	544d
536 x 10	546d
538 x 10	548d
540 x 10	550d
542 x 10	552d
544 x 10	554d
546 x 10	556d
548 x 10	558d
550 x 10	560d
552 x 10	562d
554 x 10	564d
556 x 10	566d
558 x 10	568d
560 x 10	570d
562 x 10	572d
564 x 10	574d
566 x 10	576d
568 x 10	578d
570 x 10	580d
572 x 10	582d
574 x 10	584d
576 x 10	586d
578 x 10	588d
580 x 10	590d
582 x 10	592d
584 x 10	594d
586 x 10	596d
588 x 10	598d
590 x 10	600d
592 x 10	602d
594 x 10	604d
596 x 10	606d
598 x 10	608d
600 x 10	610d
602 x 10	612d
604 x 10	614d
606 x 10	616d
608 x 10	618d
610 x 10	620d
612 x 10	622d
614 x 10	624d
616 x 10	626d
618 x 10	628d
620 x 10	630d
622 x 10	632d
624 x 10	634d
626 x 10	636d
628 x 10	638d
630 x 10	640d
632 x 10	642d
634 x 10	644d
636 x 10	646d
638 x 10	648d
640 x 10	650d
642 x 10	652d
644 x 10	654d
646 x 10	656d
648 x 10	658d
650 x 10	660d
652 x 10	662d
654 x 10	664d
656 x 10	666d
658 x 10	668d
660 x 10	670d
662 x 10	672d
664 x 10	674d
666 x 10	676d
668 x 10	678d
670 x 10	680d
672 x 10	682d
674 x 10	684d
676 x 10	686d
678 x 10	688d
680 x 10	690d
682 x 10	692d
684 x 10	694d
686 x 10	696d
688 x 10	698d
690 x 10	700d
692 x 10	702d
694 x 10	704d
696 x 10	706d
698 x 10	708d
700 x 10	710d
702 x 10	712d
704 x 10	714d
706 x 10	716d
708 x 10	718d
710 x 10	720d
712 x 10	722d
714 x 10	724d
716 x 10	726d
718 x 10	728d
720 x 10	730d
722 x 10	732d
724 x 10	734d
726 x 10	736d
728 x 10	738d
730 x 10	740d
732 x 10	742d
734 x 10	744d
736 x 10	746d
738 x 10	748d
740 x 10	750d
742 x 10	752d
744 x 10	754d
746 x 10	756d
748 x 10	758d
750 x 10	760d
752 x 10	762d
754 x 10	764d
756 x 10	766d
758 x 10	768d
760 x 10	770d
762 x 10	772d
764 x 10	774d
766 x 10	776d
768 x 10	778d
770 x 10	780d
772 x 10	782d
774 x 10	784d
776 x 10	786d
778 x 10	788d
780 x 10	790d
782 x 10	792d
784 x 10	794d
786 x 10	796d
788 x 10	798d
790 x 10	800d
792 x 10	802d
794 x 10	804d
796 x 10	806d
798 x 10	808d
800 x 10	810d
802 x 10	812d
804 x 10	814d
806 x 10	816d
808 x 10	818d
810 x 10	820d
812 x 10	822d
814 x 10	824d
816 x 10	826d
818 x 10	828d
820 x 10	830d
822 x 10	832d
824 x 10	834d
826 x 10	836d
828 x 10	838d
830 x 10	840d
832 x 10	842d
834 x 10	844d
836 x 10	846d
838 x 10	848d
840 x 10	850d
842 x 10	852d
844 x 10	854d
846 x 10	856d
848 x 10	858d
850 x 10	860d
852 x 10	862d
854 x 10	864d
856 x 10	866d
858 x 10	868d
860 x 10	870d
862 x 10	872d
864 x 10	874d
866 x 10	876d
868 x 10	878d
870 x 10	880d
872 x 10	882d
874 x 10	884d
876 x 10	886d
878 x 10	888d
880 x 10	890d
882 x 10	892d
884 x 10	894d
886 x 10	896d
888 x 10	898d
890 x 10	900d
892 x 10	902d
894 x 10	904d
896 x 10	906d
898 x 10</	

KING POST TRUSS





RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber		
2. Cable or Rods		
3. Connections		
4. Nails		
5. Hammer		
6. Saw		
7. Wedges		
8. Tape measure/yardstick, etc.		
9.		
10.		

details



DETAIL AT MIDSPAN



NAILING SCHEDULE	
BOARD SIZE (MINIMUM)	NAIL SIZE
1" x 10"	6d
2" x 10"	8d
3" x 10"	10d
4" x 10"	12d
5" x 10"	14d
6" x 10"	16d
8" x 10"	20d
10" x 10"	24d
12" x 10"	30d
14" x 10"	36d
16" x 10"	40d


where b = width of joists
 when b = 2" in. use 2 nails
 when b = 4" in. use 4 nails
 when b = 6" in. use 6 nails

RESOURCE LIST

QuantityAvailable








1. Timber (Studs & Plates)
2. Bracing Material
(Plywood Sheeting or
nom. 1-in. Timber)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
8. _____
9. _____
10. _____

details



WALLING SCHEDULE	WALL SIZE
BOARD S.I.E. (NOMINAL)	6" x 8"
1 x 6	6" x 8"
2 x 6	6" x 8"
3 x 6	6" x 8"
4 x 6	6" x 8"

* where b = width of base plate
 when b = 2" use 2 nails
 when b = 4" use 3 nails
 when b = 6" use 4 nails



STEEL-LIGHT CONSTRUCTION-Floors

OPEN-WEB JOIST






stud wall upgrading

POST & BEAM

RESOURCE LIST


<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		

details



NUMBER	SIZE (MINIMUM)	NAIL SIZE
1	1 x 12	6d
2	2 x 10	10d
3	3 x 10	10d
4	4 x 10	10d

* where 10 = width of joists
 when 1 = 2 in. use 2 nails
 when 1 = 4 in. use 3 nails
 when 1 = 6 in. use 4 nails




STEEL-LIGHT CONSTRUCTION-Floors OPEN-WEB JOIST

post & beam
upgrading

KING POST TRUSS




RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber		
2. Cable or Rods		
3. Connections		
4. Nails		
5. Hammer		
6. Saw		
7. Wedges		
8. Tape measure/yardstick, etc.		
9.		
10.		





NAME	DATE	TIME	TEMP
BOAT SIZE (MM)			
10	10	10	10
20	20	20	20
30	30	30	30
40	40	40	40
50	50	50	50


Notes: 10 = width of track
 when 10 = 2 in. MC 2 in
 when 20 = 4 in. MC 4 in
 when 30 = 6 in. MC 6 in
 when 40 = 8 in. MC 8 in
 when 50 = 10 in. MC 10 in



details



ALT: DETAIL 1



STEEL-LIGHT CONSTRUCTION-Floors


king post truss
upgrading

STUD WALL

RESOURCE LIST






<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		

details



NAILING EQUIV.	NAIL SIZE
1 X 10	6d, 8d
2 X 10	8d, 10d, 12d
3 X 10	10d, 12d, 14d
4 X 10	12d, 14d, 16d

* above 10" width of studs
when 1" = 2" in. but 2" nails
when 1" = 4" in. but 4" nails
when 1" = 6" in. but 6" nails




STEEL-HEAVY CONSTRUCTION-Floors BEAM AND SLAB

stud wall upgrading


POST & BEAM

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		



details



BEAM SIZE	WEDGES	WEDGES
1 x 10	6d, 8d	
2 x 10	8d, 10d, 12d	
3 x 10	10d, 12d, 14d	
4 x 10	12d, 14d, 16d	
* where 10 = width of flange		
when 10 = 2 in. use 6 nails		
when 10 = 4 in. use 8 nails		
when 10 = 6 in. use 10 nails		

STEEL-HEAVY CONSTRUCTION-Floors

BEAM AND SLAB


post & beam
upgrading

STUD WALL

RESOURCE LIST





<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		

details



NAILING SCHEDULE	TEE SIZE
1 x 10	6d, 8d
2 x 10	8d, 10d, 12-1
3 x 10	10d, 20d, 30d
4 x 10	40d, 50d, 60d

* where b = width of flange
 when b = 2 in. use 2 nails
 when b = 4 in. use 4 nails
 when b = 6 in. use 6 nails



CONCRETE CONSTRUCTION-Floors DOUBLE TEE



stud wall upgrading

POST & BEAM

RESOURCE LIST


<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		

details



BOARD SIZE (INCHES)	NAILING SCHEDULE
1 x 10	6d, 8d
2 x 10	8d, 10d, 12d
3 x 10	10d, 20d, 30d
4 x 10	40d, 60d, 80d

a where b = width of supports
 when b = 2 in. use 6 nails
 when b = 4 in. use 8 nails
 when b = 6 in. use 10 nails



CONCRETE CONSTRUCTION—Floors DOUBLE TEE



post & beam
upgrading

POSTS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber Posts		
2. Nails		
3. Hammer		
4. Saw		
5. Wedges		
6. Tape measure/yardstick, etc.		
7.		
8.		
9.		
10.		

details



CONCRETE CONSTRUCTION--Floors

WAFFLE SLAB

post upgrading

POSTS

RESOURCE LIST

Required

Quantity

Available

1. Timber Posts

2. Nails

3. Hammer

4. Saw

5. Wedges

6. Tape measure/yardstick, etc.



7.

8.

9.

10.

details



CONCRETE CONSTRUCTION—Floors

FLAT SLAB



post upgrading

POSTS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber Posts		
2. Nails		
3. Hammer		
4. Saw		
5. Wedges		
6. Tape measure/yardstick, etc.		
7.		
8.		
9.		
10.		

details



CONCRETE CONSTRUCTION—Floors

FLAT PLATE

post upgrading

STUD WALL

RESOURCE LIST

Available

Quantity

Required

1. Timber (Studs & Plates)

2. Bracing Material
(plywood Sheeting or
nom. 1-in. Timber)

3. Nails

4. Hammer

5. Saw

6. Wedges


7. Tape measure/yardstick, etc.

8. _____

9. _____





10. _____

details



BOARD SIZE (IN MINIMUM)	NAIL NO.	SPACING	PLAN	VIEW
1" x 10"	60d	8"	8"	8"
2" x 10"	84	10d	12"	12"
3" x 10"	10d	20d	30d	30d
4" x 10"	40d	80d	80d	80d



* where 10" = width of joists
 where 10" = 2" in 10" of joists
 where 10" = 4" in 10" of joists
 where 10" = 6" in 10" of joists



CONCRETE CONSTRUCTION—Floors ONE-WAY JOIST

stud wall upgrading

details








BOARD SIZE (MINIMUM)	NAIL SIZE
1 x 6	6d
2 x 6	8d
3 x 6	10d
4 x 6	12d
5 x 6	14d
6 x 6	16d
8 x 6	18d
10 x 6	20d
12 x 6	22d
14 x 6	24d
16 x 6	26d
18 x 6	28d
20 x 6	30d
22 x 6	32d
24 x 6	34d
26 x 6	36d
28 x 6	38d
30 x 6	40d
32 x 6	42d
34 x 6	44d
36 x 6	46d
38 x 6	48d
40 x 6	50d
42 x 6	52d
44 x 6	54d
46 x 6	56d
48 x 6	58d
50 x 6	60d
52 x 6	62d
54 x 6	64d
56 x 6	66d
58 x 6	68d
60 x 6	70d
62 x 6	72d
64 x 6	74d
66 x 6	76d
68 x 6	78d
70 x 6	80d
72 x 6	82d
74 x 6	84d
76 x 6	86d
78 x 6	88d
80 x 6	90d
82 x 6	92d
84 x 6	94d
86 x 6	96d
88 x 6	98d
90 x 6	100d
92 x 6	102d
94 x 6	104d
96 x 6	106d
98 x 6	108d
100 x 6	110d
102 x 6	112d
104 x 6	114d
106 x 6	116d
108 x 6	118d
110 x 6	120d
112 x 6	122d
114 x 6	124d
116 x 6	126d
118 x 6	128d
120 x 6	130d
122 x 6	132d
124 x 6	134d
126 x 6	136d
128 x 6	138d
130 x 6	140d
132 x 6	142d
134 x 6	144d
136 x 6	146d
138 x 6	148d
140 x 6	150d
142 x 6	152d
144 x 6	154d
146 x 6	156d
148 x 6	158d
150 x 6	160d
152 x 6	162d
154 x 6	164d
156 x 6	166d
158 x 6	168d
160 x 6	170d
162 x 6	172d
164 x 6	174d
166 x 6	176d
168 x 6	178d
170 x 6	180d
172 x 6	182d
174 x 6	184d
176 x 6	186d
178 x 6	188d
180 x 6	190d
182 x 6	192d
184 x 6	194d
186 x 6	196d
188 x 6	198d
190 x 6	200d
192 x 6	202d
194 x 6	204d
196 x 6	206d
198 x 6	208d
200 x 6	210d
202 x 6	212d
204 x 6	214d
206 x 6	216d
208 x 6	218d
210 x 6	220d
212 x 6	222d
214 x 6	224d
216 x 6	226d
218 x 6	228d
220 x 6	230d
222 x 6	232d
224 x 6	234d
226 x 6	236d
228 x 6	238d
230 x 6	240d
232 x 6	242d
234 x 6	244d
236 x 6	246d
238 x 6	248d
240 x 6	250d
242 x 6	252d
244 x 6	254d
246 x 6	256d
248 x 6	258d
250 x 6	260d
252 x 6	262d
254 x 6	264d
256 x 6	266d
258 x 6	268d
260 x 6	270d
262 x 6	272d
264 x 6	274d
266 x 6	276d
268 x 6	278d
270 x 6	280d
272 x 6	282d
274 x 6	284d
276 x 6	286d
278 x 6	288d
280 x 6	290d
282 x 6	292d
284 x 6	294d
286 x 6	296d
288 x 6	298d
290 x 6	300d
292 x 6	302d
294 x 6	304d
296 x 6	306d
298 x 6	308d
300 x 6	310d
302 x 6	312d
304 x 6	314d
306 x 6	316d
308 x 6	318d
310 x 6	320d
312 x 6	322d
314 x 6	324d
316 x 6	326d
318 x 6	328d
320 x 6	330d
322 x 6	332d
324 x 6	334d
326 x 6	336d
328 x 6	338d
330 x 6	340d
332 x 6	342d
334 x 6	344d
336 x 6	346d
338 x 6	348d
340 x 6	350d
342 x 6	352d
344 x 6	354d
346 x 6	356d
348 x 6	358d
350 x 6	360d
352 x 6	362d
354 x 6	364d
356 x 6	366d
358 x 6	368d
360 x 6	370d
362 x 6	372d
364 x 6	374d
366 x 6	376d
368 x 6	378d
370 x 6	380d
372 x 6	382d
374 x 6	384d
376 x 6	386d
378 x 6	388d
380 x 6	390d
382 x 6	392d
384 x 6	394d
386 x 6	396d
388 x 6	398d
390 x 6	400d
392 x 6	402d
394 x 6	404d
396 x 6	406d
398 x 6	408d
400 x 6	410d
402 x 6	412d
404 x 6	414d
406 x 6	416d
408 x 6	418d
410 x 6	420d
412 x 6	422d
414 x 6	424d
416 x 6	426d
418 x 6	428d
420 x 6	430d
422 x 6	432d
424 x 6	434d
426 x 6	436d
428 x 6	438d
430 x 6	440d
432 x 6	442d
434 x 6	444d
436 x 6	446d
438 x 6	448d
440 x 6	450d
442 x 6	452d
444 x 6	454d
446 x 6	456d
448 x 6	458d
450 x 6	460d
452 x 6	462d
454 x 6	464d
456 x 6	466d
458 x 6	468d
460 x 6	470d
462 x 6	472d
464 x 6	474d
466 x 6	476d
468 x 6	478d
470 x 6	480d
472 x 6	482d
474 x 6	484d
476 x 6	486d
478 x 6	488d
480 x 6	490d
482 x 6	492d
484 x 6	494d
486 x 6	496d
488 x 6	498d
490 x 6	500d
492 x 6	502d
494 x 6	504d
496 x 6	506d
498 x 6	508d
500 x 6	510d
502 x 6	512d
504 x 6	514d
506 x 6	516d
508 x 6	518d
510 x 6	520d
512 x 6	522d
514 x 6	524d
516 x 6	526d
518 x 6	528d
520 x 6	530d
522 x 6	532d
524 x 6	534d
526 x 6	536d
528 x 6	538d
530 x 6	540d
532 x 6	542d
534 x 6	544d
536 x 6	546d
538 x 6	548d
540 x 6	550d
542 x 6	552d
544 x 6	554d
546 x 6	556d
548 x 6	558d
550 x 6	560d
552 x 6	562d
554 x 6	564d
556 x 6	566d
558 x 6	568d
560 x 6	570d
562 x 6	572d
564 x 6	574d
566 x 6	576d
568 x 6	578d
570 x 6	580d
572 x 6	582d
574 x 6	584d
576 x 6	586d
578 x 6	588d
580 x 6	590d
582 x 6	592d
584 x 6	594d
586 x 6	596d
588 x 6	598d
590 x 6	600d
592 x 6	602d
594 x 6	604d
596 x 6	606d
598 x 6	608d
600 x 6	610d
602 x 6	612d
604 x 6	614d
606 x 6	616d
608 x 6	618d
610 x 6	620d
612 x 6	622d
614 x 6	624d
616 x 6	626d
618 x 6	628d
620 x 6	630d
622 x 6	632d
624 x 6	634d
626 x 6	636d
628 x 6	638d
630 x 6	640d
632 x 6	642d
634 x 6	644d
636 x 6	646d
638 x 6	648d
640 x 6	650d
642 x 6	652d
644 x 6	654d
646 x 6	656d
648 x 6	658d
650 x 6	660d
652 x 6	662d
654 x 6	664d
656 x 6	666d
658 x 6	668d
660 x 6	670d
662 x 6	672d
664 x 6	674d
666 x 6	676d
668 x 6	678d
670 x 6	680d
672 x 6	682d
674 x 6	684d
676 x 6	686d
678 x 6	688d
680 x 6	690d
682 x 6	692d
684 x 6	694d
686 x 6	696d
688 x 6	698d
690 x 6	700d
692 x 6	702d
694 x 6	704d
696 x 6	706d
698 x 6	708d
700 x 6	710d
702 x 6	712d
704 x 6	714d
706 x 6	716d
708 x 6	718d
710 x 6	720d
712 x 6	722d
714 x 6	724d
716 x 6	726d
718 x 6	728d
720 x 6	730d
722 x 6	732d
724 x 6	734d
726 x 6	736d
728 x 6	738d
730 x 6	740d
732 x 6	742d
734 x 6	744d
736 x 6	746d
738 x 6	748d
740 x 6	750d
742 x 6	752d
744 x 6	754d
746 x 6	756d
748 x 6	758d
750 x 6	760d
752 x 6	762d
754 x 6	764d
756 x 6	766d
758 x 6	768d
760 x 6	770d
762 x 6	772d
764 x 6	774d
766 x 6	776d
768 x 6	778d
770 x 6	780d
772 x 6	782d
774 x 6	784d
776 x 6	786d
778 x 6	788d
780 x 6	790d
782 x 6	792d
784 x 6	794d
786 x 6	796d
788 x 6	798d
790 x 6	800d
792 x 6	802d
794 x 6	804d
796 x 6	806d
798 x 6	808d
800 x 6	810d
802 x 6	812d
804 x 6	814d
806 x 6	816d
808 x 6	818d
810 x 6	820d
812 x 6	822d
814 x 6	824d
816 x 6	826d
818 x 6	828d
820 x 6	830d
822 x 6	832d
824 x 6	834d
826 x 6	836d
828 x 6	838d
830 x 6	840d
832 x 6	842d
834 x 6	844d
836 x 6	846d
838 x 6	848d
840 x 6	850d
842 x 6	852d
844 x 6	854d
846 x 6	856d
848 x 6	858d
850 x 6	860d
852 x 6	862d
854 x 6	864d
856 x 6	866d
858 x 6	868d
860 x 6	870d
862 x 6	872d
864 x 6	874d
866 x 6	876d
868 x 6	878d
870 x 6	880d
872 x 6	882d
874 x 6	884d
876 x 6	886d
878 x 6	888d
880 x 6	890d
882 x 6	892d
884 x 6	894d
886 x 6	896d
888 x 6	898d
890 x 6	900d
892 x 6	902d
894 x 6	904d
896 x 6	906d
898 x 6	908d
900 x 6	910d
902 x 6	912d
904 x 6	914d
906 x 6	916d
908 x 6	918d
910 x 6	920d
912 x 6	922d
914 x 6	924d
916 x 6	926d
918 x 6	928d
920 x 6	930d
922 x 6	932d
924 x 6	934d
926 x 6	936d
928 x 6	938d
930 x 6	940d
932 x 6	942d
934 x 6	944d

STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		

details



BOARD SIZE (IN. NOMINAL)	SPACING (IN.)	MAX. STUD SIZE (IN. NOMINAL)
1 x 4	12	4
2 x 4	12	4
3 x 4	12	4
4 x 4	12	4

* where p = width of joists
 where p = 2 in. max. joist
 where p = 4 in. max. joist
 where p = 6 in. max. joist

CONCRETE CONSTRUCTION—Floors

HOLLOW-CORE

stud wall upgrading



RESOURCE LIST

Required

QuantityAvailable


1. Timber (Posts)
2. Timber (Beams)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
8. _____
9. _____
10. _____

details



NAILING SCHEDULE	
BOARD SIZE (MINIMUM)	NAIL SIZE
1 x 12	6d, 8d
2 x 12	8d, 10d, 12d
3 x 12	10d, 20d, 30d
4 x 12	40d, 50d, 60d

* where b = width of boards
 when b = 2 in. use 2 nails
 when b = 4 in. use 3 nails
 when b = 6 in. use 4 nails



CONCRETE CONSTRUCTION-Floors

HOLLOW-CORE



post & beam
upgrading

ROOFS


STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)	_____	_____
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)	_____	_____
3. Nails	_____	_____
4. Hammer	_____	_____
5. Saw	_____	_____
6. Wedges	_____	_____
7. Tape measure/yardstick, etc.	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____






details



NAILED TO STUD (MINIMUM)	NAILED TO STUD
1 x 12	6d, 12d
2 x 12	8d, 12d, 16d
3 x 12	10d, 12d, 16d
4 x 12	12d, 16d, 20d

* where 12d with 12d bolts
where 16d with 16d bolts
where 20d with 20d bolts



THIS PAGE IS BEST QUALITY FRACITABLE
FROM ONLY FOR INFORMATION

WOOD CONSTRUCTION-ROOFS TIMBER JOIST

stud wall upgrading

POST & BEAM

RESOURCE LIST

Required




1. Timber (Posts)
2. Timber (Beams)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
- 8.
- 9.
- 10.

Quantity

Available

post & beam
upgrading

details





NAILING QUIPSET		PDA D SPT		PDA D SPT	
NO	DATE	NO	DATE	NO	DATE
1	1/1/19	1	1/1/19	1	1/1/19
2	1/1/19	2	1/1/19	2	1/1/19
3	1/1/19	3	1/1/19	3	1/1/19
4	1/1/19	4	1/1/19	4	1/1/19
5	1/1/19	5	1/1/19	5	1/1/19
6	1/1/19	6	1/1/19	6	1/1/19
7	1/1/19	7	1/1/19	7	1/1/19
8	1/1/19	8	1/1/19	8	1/1/19
9	1/1/19	9	1/1/19	9	1/1/19
10	1/1/19	10	1/1/19	10	1/1/19
11	1/1/19	11	1/1/19	11	1/1/19
12	1/1/19	12	1/1/19	12	1/1/19
13	1/1/19	13	1/1/19	13	1/1/19
14	1/1/19	14	1/1/19	14	1/1/19
15	1/1/19	15	1/1/19	15	1/1/19
16	1/1/19	16	1/1/19	16	1/1/19
17	1/1/19	17	1/1/19	17	1/1/19
18	1/1/19	18	1/1/19	18	1/1/19
19	1/1/19	19	1/1/19	19	1/1/19
20	1/1/19	20	1/1/19	20	1/1/19
21	1/1/19	21	1/1/19	21	1/1/19
22	1/1/19	22	1/1/19	22	1/1/19
23	1/1/19	23	1/1/19	23	1/1/19
24	1/1/19	24	1/1/19	24	1/1/19
25	1/1/19	25	1/1/19	25	1/1/19
26	1/1/19	26	1/1/19	26	1/1/19
27	1/1/19	27	1/1/19	27	1/1/19
28	1/1/19	28	1/1/19	28	1/1/19
29	1/1/19	29	1/1/19	29	1/1/19
30	1/1/19	30	1/1/19	30	1/1/19
31	1/1/19	31	1/1/19	31	1/1/19
32	1/1/19	32	1/1/19	32	1/1/19
33	1/1/19	33	1/1/19	33	1/1/19
34	1/1/19	34	1/1/19	34	1/1/19
35	1/1/19	35	1/1/19	35	1/1/19
36	1/1/19	36	1/1/19	36	1/1/19
37	1/1/19	37	1/1/19	37	1/1/19
38	1/1/19	38	1/1/19	38	1/1/19
39	1/1/19	39	1/1/19	39	1/1/19
40	1/1/19	40	1/1/19	40	1/1/19
41	1/1/19	41	1/1/19	41	1/1/19
42	1/1/19	42	1/1/19	42	1/1/19
43	1/1/19	43	1/1/19	43	1/1/19
44	1/1/19	44	1/1/19	44	1/1/19
45	1/1/19	45	1/1/19	45	1/1/19
46	1/1/19	46	1/1/19	46	1/1/19
47	1/1/19	47	1/1/19	47	1/1/19
48	1/1/19	48	1/1/19	48	1/1/19
49	1/1/19	49	1/1/19	49	1/1/19
50	1/1/19	50	1/1/19	50	1/1/19
51	1/1/19	51	1/1/19	51	1/1/19
52	1/1/19	52	1/1/19	52	1/1/19
53	1/1/19	53	1/1/19	53	1/1/19
54	1/1/19	54	1/1/19	54	1/1/19
55	1/1/19	55	1/1/19	55	1/1/19
56	1/1/19	56	1/1/19	56	1/1/19
57	1/1/19	57	1/1/19	57	1/1/19
58	1/1/19	58	1/1/19	58	1/1/19
59	1/1/19	59	1/1/19	59	1/1/19
60	1/1/19	60	1/1/19	60	1/


STUD WALL

RESOURCE LIST



<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		



details



ITEM NO.	DESCRIPTION	QTY.	UNIT
1	2x4x8 (12'x12')	1	EA.
2	2x4x8 (12'x12')	1	EA.
3	2x4x8 (12'x12')	1	EA.
4	2x4x8 (12'x12')	1	EA.
5	2x4x8 (12'x12')	1	EA.
6	2x4x8 (12'x12')	1	EA.
7	2x4x8 (12'x12')	1	EA.
8	2x4x8 (12'x12')	1	EA.
9	2x4x8 (12'x12')	1	EA.
10	2x4x8 (12'x12')	1	EA.



THIS PAGE IS FOR A QUALITY FRANCHISE
FROM OUR FURNISHING TO YOU

WOOD CONSTRUCTION-ROOFS


GLULAM

stud wall upgrading



POST & BEAM

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		



details



Beam	Size	Spacing	Post	Post
1 x 10	6d	10d	6d	10d
2 x 10	6d	10d	12d	12d
3 x 10	6d	10d	12d	12d
4 x 10	6d	10d	12d	12d
4 x 10	6d	10d	12d	12d

Notes: 1. All posts shall be 12d or larger.
2. All beams shall be 10d or larger.
3. All posts shall be 12d or larger.
4. All beams shall be 10d or larger.

THIS DRAWING IS THE PROPERTY OF THE U.S. FOREST SERVICE AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.

WOOD CONSTRUCTION—Roofs

GLULAM

post & beam
upgrading

STUD WALL



RESOURCE LIST

Required


1. Timber (Studs & Plates)
2. Bracing Material
(Plywood Sheeting or
nom. 1-in. Timber)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
8. _____
9. _____
10. _____

Quantity





Available



details



JOIST SIZE	MAX. SPAN	MAX. JOIST
12" x 12"	12'-0"	12'-0"
12" x 14"	14'-0"	14'-0"
12" x 16"	16'-0"	16'-0"
12" x 18"	18'-0"	18'-0"
12" x 20"	20'-0"	20'-0"
12" x 22"	22'-0"	22'-0"
12" x 24"	24'-0"	24'-0"
12" x 26"	26'-0"	26'-0"
12" x 28"	28'-0"	28'-0"
12" x 30"	30'-0"	30'-0"
12" x 32"	32'-0"	32'-0"
12" x 34"	34'-0"	34'-0"
12" x 36"	36'-0"	36'-0"
12" x 38"	38'-0"	38'-0"
12" x 40"	40'-0"	40'-0"
12" x 42"	42'-0"	42'-0"
12" x 44"	44'-0"	44'-0"
12" x 46"	46'-0"	46'-0"
12" x 48"	48'-0"	48'-0"
12" x 50"	50'-0"	50'-0"
12" x 52"	52'-0"	52'-0"
12" x 54"	54'-0"	54'-0"
12" x 56"	56'-0"	56'-0"
12" x 58"	58'-0"	58'-0"
12" x 60"	60'-0"	60'-0"
12" x 62"	62'-0"	62'-0"
12" x 64"	64'-0"	64'-0"
12" x 66"	66'-0"	66'-0"
12" x 68"	68'-0"	68'-0"
12" x 70"	70'-0"	70'-0"
12" x 72"	72'-0"	72'-0"
12" x 74"	74'-0"	74'-0"
12" x 76"	76'-0"	76'-0"
12" x 78"	78'-0"	78'-0"
12" x 80"	80'-0"	80'-0"
12" x 82"	82'-0"	82'-0"
12" x 84"	84'-0"	84'-0"
12" x 86"	86'-0"	86'-0"
12" x 88"	88'-0"	88'-0"
12" x 90"	90'-0"	90'-0"
12" x 92"	92'-0"	92'-0"
12" x 94"	94'-0"	94'-0"
12" x 96"	96'-0"	96'-0"
12" x 98"	98'-0"	98'-0"
12" x 100"	100'-0"	100'-0"




STEEL LIGHT CONSTRUCTION--ROOFS OPEN-WEB JOIST

stud wall upgrading

POST & BEAM

RESOURCE LIST


<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		



THIS PAGE IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.

POWDER	TEMPERATURE	PLATE SIZE
1	200	4x4
2	200	4x4
3	200	4x4
4	200	4x4

where 4x4 = width of plates
 where 200 = 2 in. over 2 in.
 where 4x4 = 4 in. over 4 in.
 where 200 = 200 in. over 200 in.



STEEL LIGHT CONSTRUCTION-ROOFS




post & beam
upgrading

STUD WALL



RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		


details



NAILING SCHEDULE	NAIL SIZE
1 x 4	6d
2 x 4	8d
4 x 4	10d
6 x 6	12d
8 x 8	14d
10 x 10	16d
12 x 12	18d
14 x 14	20d
16 x 16	22d
18 x 18	24d
20 x 20	26d
22 x 22	28d
24 x 24	30d
26 x 26	32d
28 x 28	34d
30 x 30	36d
32 x 32	38d
34 x 34	40d
36 x 36	42d
38 x 38	44d
40 x 40	46d
42 x 42	48d
44 x 44	50d
46 x 46	52d
48 x 48	54d
50 x 50	56d
52 x 52	58d
54 x 54	60d
56 x 56	62d
58 x 58	64d
60 x 60	66d
62 x 62	68d
64 x 64	70d
66 x 66	72d
68 x 68	74d
70 x 70	76d
72 x 72	78d
74 x 74	80d
76 x 76	82d
78 x 78	84d
80 x 80	86d
82 x 82	88d
84 x 84	90d
86 x 86	92d
88 x 88	94d
90 x 90	96d
92 x 92	98d
94 x 94	100d
96 x 96	102d
98 x 98	104d
100 x 100	106d
102 x 102	108d
104 x 104	110d
106 x 106	112d
108 x 108	114d
110 x 110	116d
112 x 112	118d
114 x 114	120d
116 x 116	122d
118 x 118	124d
120 x 120	126d
122 x 122	128d
124 x 124	130d
126 x 126	132d
128 x 128	134d
130 x 130	136d
132 x 132	138d
134 x 134	140d
136 x 136	142d
138 x 138	144d
140 x 140	146d
142 x 142	148d
144 x 144	150d
146 x 146	152d
148 x 148	154d
150 x 150	156d
152 x 152	158d
154 x 154	160d
156 x 156	162d
158 x 158	164d
160 x 160	166d
162 x 162	168d
164 x 164	170d
166 x 166	172d
168 x 168	174d
170 x 170	176d
172 x 172	178d
174 x 174	180d
176 x 176	182d
178 x 178	184d
180 x 180	186d
182 x 182	188d
184 x 184	190d
186 x 186	192d
188 x 188	194d
190 x 190	196d
192 x 192	198d
194 x 194	200d
196 x 196	202d
198 x 198	204d
200 x 200	206d
202 x 202	208d
204 x 204	210d
206 x 206	212d
208 x 208	214d
210 x 210	216d
212 x 212	218d
214 x 214	220d
216 x 216	222d
218 x 218	224d
220 x 220	226d
222 x 222	228d
224 x 224	230d
226 x 226	232d
228 x 228	234d
230 x 230	236d
232 x 232	238d
234 x 234	240d
236 x 236	242d
238 x 238	244d
240 x 240	246d
242 x 242	248d
244 x 244	250d
246 x 246	252d
248 x 248	254d
250 x 250	256d
252 x 252	258d
254 x 254	260d
256 x 256	262d
258 x 258	264d
260 x 260	266d
262 x 262	268d
264 x 264	270d
266 x 266	272d
268 x 268	274d
270 x 270	276d
272 x 272	278d
274 x 274	280d
276 x 276	282d
278 x 278	284d
280 x 280	286d
282 x 282	288d
284 x 284	290d
286 x 286	292d
288 x 288	294d
290 x 290	296d
292 x 292	298d
294 x 294	300d
296 x 296	302d
298 x 298	304d
300 x 300	306d
302 x 302	308d
304 x 304	310d
306 x 306	312d
308 x 308	314d
310 x 310	316d
312 x 312	318d
314 x 314	320d
316 x 316	322d
318 x 318	324d
320 x 320	326d
322 x 322	328d
324 x 324	330d
326 x 326	332d
328 x 328	334d
330 x 330	336d
332 x 332	338d
334 x 334	340d
336 x 336	342d
338 x 338	344d
340 x 340	346d
342 x 342	348d
344 x 344	350d
346 x 346	352d
348 x 348	354d
350 x 350	356d
352 x 352	358d
354 x 354	360d
356 x 356	362d
358 x 358	364d
360 x 360	366d
362 x 362	368d
364 x 364	370d
366 x 366	372d
368 x 368	374d
370 x 370	376d
372 x 372	378d
374 x 374	380d
376 x 376	382d
378 x 378	384d
380 x 380	386d
382 x 382	388d
384 x 384	390d
386 x 386	392d
388 x 388	394d
390 x 390	396d
392 x 392	398d
394 x 394	400d
396 x 396	402d
398 x 398	404d
400 x 400	406d
402 x 402	408d
404 x 404	410d
406 x 406	412d
408 x 408	414d
410 x 410	416d
412 x 412	418d
414 x 414	420d
416 x 416	422d
418 x 418	424d
420 x 420	426d
422 x 422	428d
424 x 424	430d
426 x 426	432d
428 x 428	434d
430 x 430	436d
432 x 432	438d
434 x 434	440d
436 x 436	442d
438 x 438	444d
440 x 440	446d
442 x 442	448d
444 x 444	450d
446 x 446	452d
448 x 448	454d
450 x 450	456d
452 x 452	458d
454 x 454	460d
456 x 456	462d
458 x 458	464d
460 x 460	466d
462 x 462	468d
464 x 464	470d
466 x 466	472d
468 x 468	474d
470 x 470	476d
472 x 472	478d
474 x 474	480d
476 x 476	482d
478 x 478	484d
480 x 480	486d
482 x 482	488d
484 x 484	490d
486 x 486	492d
488 x 488	494d
490 x 490	496d
492 x 492	498d
494 x 494	500d
496 x 496	502d
498 x 498	504d
500 x 500	506d
502 x 502	508d
504 x 504	510d
506 x 506	512d
508 x 508	514d
510 x 510	516d
512 x 512	518d
514 x 514	520d
516 x 516	522d
518 x 518	524d
520 x 520	526d
522 x 522	528d
524 x 524	530d
526 x 526	532d
528 x 528	534d
530 x 530	536d
532 x 532	538d
534 x 534	540d
536 x 536	542d
538 x 538	544d
540 x 540	546d
542 x 542	548d
544 x 544	550d
546 x 546	552d
548 x 548	554d
550 x 550	556d
552 x 552	558d
554 x 554	560d
556 x 556	562d
558 x 558	564d
560 x 560	566d
562 x 562	568d
564 x 564	570d
566 x 566	572d
568 x 568	574d
570 x 570	576d
572 x 572	578d
574 x 574	580d
576 x 576	582d
578 x 578	584d
580 x 580	586d
582 x 582	588d
584 x 584	590d
586 x 586	592d
588 x 588	594d
590 x 590	596d
592 x 592	598d
594 x 594	600d
596 x 596	602d
598 x 598	604d
600 x 600	606d
602 x 602	608d
604 x 604	610d
606 x 606	612d
608 x 608	614d
610 x 610	616d
612 x 612	618d
614 x 614	620d
616 x 616	622d
618 x 618	624d
620 x 620	626d
622 x 622	628d
624 x 624	630d
626 x 626	632d
628 x 628	634d
630 x 630	636d
632 x 632	638d
634 x 634	640d
636 x 636	642d
638 x 638	644d
640 x 640	646d
642 x 642	648d
644 x 644	650d
646 x 646	652d
648 x 648	654d
650 x 650	656d
652 x 652	658d
654 x 654	660d
656 x 656	662d
658 x 658	664d
660 x 660	666d
662 x 662	668d
664 x 664	670d
666 x 666	672d
668 x 668	674d
670 x 670	676d
672 x 672	678d
674 x 674	680d
676 x 676	682d
678 x 678	684d
680 x 680	686d
682 x 682	688d
684 x 684	690d
686 x 686	692d
688 x 688	694d
690 x 690	696d
692 x 692	698d
694 x 694	700d
696 x 696	702d
698 x 698	704d
700 x 700	706d
702 x 702	708d
704 x 704	710d
706 x 706	712d
708 x 708	714d
710 x 710	716d
712 x 712	718d
714 x 714	720d
716 x 716	722d
718 x 718	724d
720 x 720	726d
722 x 722	728d
724 x 724	730d
726 x 726	732d
728 x 728	734d
730 x 730	736d
732 x 732	738d
734 x 734	740d
736 x 736	742d
738 x 738	744d
740 x 740	746d
742 x 742	748d
744 x 744	750d
746 x 746	752d
748 x 748	754d
750 x 750	756d
752 x 752	758d
754 x 754	760d
756 x 756	762d
758 x 758	764d
760 x 760	766d
762 x 762	768d
764 x 764	770d
766 x 766	772d
768 x 768	774d
770 x 770	776d
772 x 772	778d
774 x 774	780d
776 x 776	782d
778 x 778	784d
780 x 780	786d
782 x 782	788d
784 x 784	790d
786 x 786	792d
788 x 788	794d
790 x 790	796d
792 x 792	798d
794 x 794	800d
796 x 796	802d
798 x 798	804d
800 x 800	806d
802 x 802	808d
804 x 804	810d
806 x 806	812d
808 x 808	814d
810 x 810	816d
812 x 812	818d
814 x 814	820d
816 x 816	822d
818 x 818	824d
820 x 820	826d
822 x 822	828d
824 x 824	830d
826 x 826	832d
828 x 828	834d
830 x 830	836d
832 x 832	838d
834 x 834	840d
836 x 836	842d
838 x 838	844d
840 x 840	846d
842 x 842	848d
844 x 844	850d
846 x 846	852d
848 x 848	854d
850 x 850	856d
852 x 852	858d
854 x 854	860d
856 x 856	862d
858 x 858	864d
860 x 860	866d
862 x 862	868d
864 x 864	870d
866 x 866	872d
868 x 868	874d
870 x 870	876d
872 x 872	878d






OPEN-WEB
STEEL JOIST



INSULATION
PLYWOOD OR
METAL DECKING
BUILT-UP ROOF
OPEN-WEB
STEEL
JOIST

details




NAILING SCHEDULE	JOIST SIZE
1 x 6	6d, 8d
2 x 6	8d, 10d, 12d
3 x 6	10d, 12d, 14d
4 x 6	12d, 14d, 16d
6 x 6	14d, 16d, 18d
8 x 6	16d, 18d, 20d
10 x 6	18d, 20d, 22d
12 x 6	20d, 22d, 24d
14 x 6	22d, 24d, 26d
16 x 6	24d, 26d, 28d
18 x 6	26d, 28d, 30d
20 x 6	28d, 30d, 32d
22 x 6	30d, 32d, 34d
24 x 6	32d, 34d, 36d
26 x 6	34d, 36d, 38d
28 x 6	36d, 38d, 40d
30 x 6	38d, 40d, 42d
32 x 6	40d, 42d, 44d
34 x 6	42d, 44d, 46d
36 x 6	44d, 46d, 48d
38 x 6	46d, 48d, 50d
40 x 6	48d, 50d, 52d
42 x 6	50d, 52d, 54d
44 x 6	52d, 54d, 56d
46 x 6	54d, 56d, 58d
48 x 6	56d, 58d, 60d
50 x 6	58d, 60d, 62d
52 x 6	60d, 62d, 64d
54 x 6	62d, 64d, 66d
56 x 6	64d, 66d, 68d
58 x 6	66d, 68d, 70d
60 x 6	68d, 70d, 72d
62 x 6	70d, 72d, 74d
64 x 6	72d, 74d, 76d
66 x 6	74d, 76d, 78d
68 x 6	76d, 78d, 80d
70 x 6	78d, 80d, 82d
72 x 6	80d, 82d, 84d
74 x 6	82d, 84d, 86d
76 x 6	84d, 86d, 88d
78 x 6	86d, 88d, 90d
80 x 6	88d, 90d, 92d
82 x 6	90d, 92d, 94d
84 x 6	92d, 94d, 96d
86 x 6	94d, 96d, 98d
88 x 6	96d, 98d, 100d
90 x 6	98d, 100d, 102d
92 x 6	100d, 102d, 104d
94 x 6	102d, 104d, 106d
96 x 6	104d, 106d, 108d
98 x 6	106d, 108d, 110d
100 x 6	108d, 110d, 112d
102 x 6	110d, 112d, 114d
104 x 6	112d, 114d, 116d
106 x 6	114d, 116d, 118d
108 x 6	116d, 118d, 120d
110 x 6	118d, 120d, 122d
112 x 6	120d, 122d, 124d
114 x 6	122d, 124d, 126d
116 x 6	124d, 126d, 128d
118 x 6	126d, 128d, 130d
120 x 6	128d, 130d, 132d
122 x 6	130d, 132d, 134d
124 x 6	132d, 134d, 136d
126 x 6	134d, 136d, 138d
128 x 6	136d, 138d, 140d
130 x 6	138d, 140d, 142d
132 x 6	140d, 142d, 144d
134 x 6	142d, 144d, 146d
136 x 6	144d, 146d, 148d
138 x 6	146d, 148d, 150d
140 x 6	148d, 150d, 152d
142 x 6	150d, 152d, 154d
144 x 6	152d, 154d, 156d
146 x 6	154d, 156d, 158d
148 x 6	156d, 158d, 160d
150 x 6	158d, 160d, 162d
152 x 6	160d, 162d, 164d
154 x 6	162d, 164d, 166d
156 x 6	164d, 166d, 168d
158 x 6	166d, 168d, 170d
160 x 6	168d, 170d, 172d
162 x 6	170d, 172d, 174d
164 x 6	172d, 174d, 176d
166 x 6	174d, 176d, 178d
168 x 6	176d, 178d, 180d
170 x 6	178d, 180d, 182d
172 x 6	180d, 182d, 184d
174 x 6	182d, 184d, 186d
176 x 6	184d, 186d, 188d
178 x 6	186d, 188d, 190d
180 x 6	188d, 190d, 192d
182 x 6	190d, 192d, 194d
184 x 6	192d, 194d, 196d
186 x 6	194d, 196d, 198d
188 x 6	196d, 198d, 200d
190 x 6	198d, 200d, 202d
192 x 6	200d, 202d, 204d
194 x 6	202d, 204d, 206d
196 x 6	204d, 206d, 208d
198 x 6	206d, 208d, 210d
200 x 6	208d, 210d, 212d
202 x 6	210d, 212d, 214d
204 x 6	212d, 214d, 216d
206 x 6	214d, 216d, 218d
208 x 6	216d, 218d, 220d
210 x 6	218d, 220d, 222d
212 x 6	220d, 222d, 224d
214 x 6	222d, 224d, 226d
216 x 6	224d, 226d, 228d
218 x 6	226d, 228d, 230d
220 x 6	228d, 230d, 232d
222 x 6	230d, 232d, 234d
224 x 6	232d, 234d, 236d
226 x 6	234d, 236d, 238d
228 x 6	236d, 238d, 240d
230 x 6	238d, 240d, 242d
232 x 6	240d, 242d, 244d
234 x 6	242d, 244d, 246d
236 x 6	244d, 246d, 248d
238 x 6	246d, 248d, 250d
240 x 6	248d, 250d, 252d
242 x 6	250d, 252d, 254d
244 x 6	252d, 254d, 256d
246 x 6	254d, 256d, 258d
248 x 6	256d, 258d, 260d
250 x 6	258d, 260d, 262d
252 x 6	260d, 262d, 264d
254 x 6	262d, 264d, 266d
256 x 6	264d, 266d, 268d
258 x 6	266d, 268d, 270d
260 x 6	268d, 270d, 272d
262 x 6	270d, 272d, 274d
264 x 6	272d, 274d, 276d
266 x 6	274d, 276d, 278d
268 x 6	276d, 278d, 280d
270 x 6	278d, 280d, 282d
272 x 6	280d, 282d, 284d
274 x 6	282d, 284d, 286d
276 x 6	284d, 286d, 288d
278 x 6	286d, 288d, 290d
280 x 6	288d, 290d, 292d
282 x 6	290d, 292d, 294d
284 x 6	292d, 294d, 296d
286 x 6	294d, 296d, 298d
288 x 6	296d, 298d, 300d
290 x 6	298d, 300d, 302d
292 x 6	300d, 302d, 304d
294 x 6	302d, 304d, 306d
296 x 6	304d, 306d, 308d
298 x 6	306d, 308d, 310d
300 x 6	308d, 310d, 312d
302 x 6	310d, 312d, 314d
304 x 6	312d, 314d, 316d
306 x 6	314d, 316d, 318d
308 x 6	316d, 318d, 320d
310 x 6	318d, 320d, 322d
312 x 6	320d, 322d, 324d
314 x 6	322d, 324d, 326d
316 x 6	324d, 326d, 328d
318 x 6	326d, 328d, 330d
320 x 6	328d, 330d, 332d
322 x 6	330d, 332d, 334d
324 x 6	332d, 334d, 336d
326 x 6	334d, 336d, 338d
328 x 6	336d, 338d, 340d
330 x 6	338d, 340d, 342d
332 x 6	340d, 342d, 344d
334 x 6	342d, 344d, 346d
336 x 6	344d, 346d, 348d
338 x 6	346d, 348d, 350d
340 x 6	348d, 350d, 352d
342 x 6	350d, 352d, 354d
344 x 6	352d, 354d, 356d
346 x 6	354d, 356d, 358d
348 x 6	356d, 358d, 360d
350 x 6	358d, 360d, 362d
352 x 6	360d, 362d, 364d
354 x 6	362d, 364d, 366d
356 x 6	364d, 366d, 368d
358 x 6	366d, 368d, 370d
360 x 6	368d, 370d, 372d
362 x 6	370d, 372d, 374d
364 x 6	372d, 374d, 376d
366 x 6	374d, 376d, 378d
368 x 6	376d, 378d, 380d
370 x 6	378d, 380d, 382d
372 x 6	380d, 382d, 384d
374 x 6	382d, 384d, 386d
376 x 6	384d, 386d, 388d
378 x 6	386d, 388d, 390d
380 x 6	388d, 390d, 392d
382 x 6	390d, 392d, 394d
384 x 6	392d, 394d, 396d
386 x 6	394d, 396d, 398d
388 x 6	396d, 398d, 400d
390 x 6	398d, 400d, 402d
392 x 6	400d, 402d, 404d
394 x 6	402d, 404d, 406d
396 x 6	404d, 406d, 408d
398 x 6	406d, 408d, 410d
400 x 6	408d, 410d, 412d
402 x 6	410d, 412d, 414d
404 x 6	412d, 414d, 416d
406 x 6	414d, 416d, 418d
408 x 6	416d, 418d, 420d
410 x 6	418d, 420d, 422d
412 x 6	420d, 422d, 424d
414 x 6	422d, 424d, 426d
416 x 6	424d, 426d, 428d
418 x 6	426d, 428d, 430d
420 x 6	428d, 430d, 432d
422 x 6	430d, 432d, 434d
424 x 6	432d, 434d, 436d
426 x 6	434d, 436d, 438d
428 x 6	436d, 438d, 440d
430 x 6	438d, 440d, 442d
432 x 6	440d, 442d, 444d
434 x 6	442d, 444d, 446d
436 x 6	444d, 446d, 448d
438 x 6	446d, 448d, 450d
440 x 6	448d, 450d, 452d
442 x 6	450d, 452d, 454d
444 x 6	452d, 454d, 456d
446 x 6	454d, 456d, 458d
448 x 6	456d, 458d, 460d
450 x 6	458d, 460d, 462d
452 x 6	460d, 462d, 464d
454 x 6	462d, 464d, 466d
456 x 6	464d, 466d, 468d
458 x 6	466d, 468d, 470d
460 x 6	468d, 470d, 472d
462 x 6	470d, 472d, 474d
464 x 6	472d, 474d, 476d
466 x 6	474d, 476d, 478d
468 x 6	476d, 478d, 480d
470 x 6	478d, 480d, 482d
472 x 6	480d, 482d, 484d
474 x 6	482d, 484d, 486d
476 x 6	484d, 486d, 488d
478 x 6	486d, 488d, 490d
480 x 6	488d, 490d, 492d
482 x 6	490d, 492d, 494d
484 x 6	492d, 494d, 496d
486 x 6	494d, 496d, 498d
488 x 6	496d, 498d, 500d
490 x 6	498d, 500d, 502d
492 x 6	500d, 502d, 504d
494 x 6	502d, 504d, 506d
496 x 6	504d, 506d, 508d
498 x 6	506d, 508d, 510d
500 x 6	508d, 510d, 512d
502 x 6	510d, 512d, 514d
504 x 6	512d, 514d, 516d
506 x 6	514d, 516d, 518d
508 x 6	516d, 518d, 520d
510 x 6	518d, 520d, 522d
512 x 6	520d, 522d, 524d
514 x 6	522d, 524d, 526d
516 x 6	524d, 526d, 528d
518 x 6	526d, 528d, 530d
520 x 6	528d, 530d, 532d
522 x 6	530d, 532d, 534d
524 x 6	532d, 534d, 536d
526 x 6	534d, 536d, 538d
528 x 6	536d, 538d, 540d
530 x 6	538d, 540d, 542d
532 x 6	540d, 542d, 544d
534 x 6	542d, 544d, 546d
536 x 6	544d, 546d, 548d
538 x 6	546d, 548d, 550d
540 x 6	548d, 550d, 552d
542 x 6	550d, 552d, 554d
544 x 6	552d, 554d, 556d
546 x 6	554d, 556d, 558d
548 x 6	556d, 558d, 560d
550 x 6	558d, 560d, 562d
552 x 6	560d, 562d, 564d
554 x 6	562d, 564d, 566d
556 x 6	564d, 566d, 568d
558 x 6	566d, 568d, 570d
560 x 6	568d, 570d, 572d
562 x 6	570d, 572d, 574d
564 x 6	572d, 574d, 576d
566 x 6	574d, 576d, 578d
568 x 6	576d, 578d, 580d
570 x 6	578d, 580d, 582d
572 x 6	580d, 582d, 584d
574 x 6	582d, 584d, 586d
576 x 6	584d, 586d, 588d
578 x 6	586d, 588d, 590d
580 x 6	588d, 590d, 592d
582 x 6	590d, 592d, 594d
584 x 6	592d, 594d, 596d
586 x 6	594d, 596d, 598d
588 x 6	596d, 598d, 600d
590 x 6	598d, 600d, 602d
592 x 6	600d, 602d, 604d
594 x 6	602d, 604d, 606d
596 x 6	604d, 606d, 608d
598 x 6	606d, 608d, 610d
600 x 6	608d, 610d, 612d
602 x 6	610d, 612d, 614d
604 x 6	612d, 614d, 616d
606 x 6	614d, 616d, 618d
608 x 6	616d, 618d, 620d
610 x 6	618d, 620d, 622d
612 x 6	620d, 622d, 624d
614 x 6	622d, 624d, 626d
616 x 6	624d, 626d, 628d
618 x 6	626d, 628d, 630d
620 x 6	628d, 630d, 632d
622 x 6	630d, 632d, 634d
624 x 6	632d, 634d, 636d
626 x 6	634d, 636d, 638d
628 x 6	636d, 638d, 640d
630 x 6	638d, 640d, 642d
632 x 6	640d, 642d





STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		



details

[illegible]


CONCRETE CONSTRUCTION-ROOFS

stud wall: upgrading



POST & BEAM

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		



details



NO.	QTY.	UNIT	PRICE	TOTAL
1	1	EA	1.00	1.00
2	1	EA	1.00	1.00
3	1	EA	1.00	1.00
4	1	EA	1.00	1.00
5	1	EA	1.00	1.00
6	1	EA	1.00	1.00
7	1	EA	1.00	1.00
8	1	EA	1.00	1.00
9	1	EA	1.00	1.00
10	1	EA	1.00	1.00
11	1	EA	1.00	1.00
12	1	EA	1.00	1.00
13	1	EA	1.00	1.00
14	1	EA	1.00	1.00
15	1	EA	1.00	1.00
16	1	EA	1.00	1.00
17	1	EA	1.00	1.00
18	1	EA	1.00	1.00
19	1	EA	1.00	1.00
20	1	EA	1.00	1.00
21	1	EA	1.00	1.00
22	1	EA	1.00	1.00
23	1	EA	1.00	1.00
24	1	EA	1.00	1.00
25	1	EA	1.00	1.00
26	1	EA	1.00	1.00
27	1	EA	1.00	1.00
28	1	EA	1.00	1.00
29	1	EA	1.00	1.00
30	1	EA	1.00	1.00
31	1	EA	1.00	1.00
32	1	EA	1.00	1.00
33	1	EA	1.00	1.00
34	1	EA	1.00	1.00
35	1	EA	1.00	1.00
36	1	EA	1.00	1.00
37	1	EA	1.00	1.00
38	1	EA	1.00	1.00
39	1	EA	1.00	1.00
40	1	EA	1.00	1.00
41	1	EA	1.00	1.00
42	1	EA	1.00	1.00
43	1	EA	1.00	1.00
44	1	EA	1.00	1.00
45	1	EA	1.00	1.00
46	1	EA	1.00	1.00
47	1	EA	1.00	1.00
48	1	EA	1.00	1.00
49	1	EA	1.00	1.00
50	1	EA	1.00	1.00
51	1	EA	1.00	1.00
52	1	EA	1.00	1.00
53	1	EA	1.00	1.00
54	1	EA	1.00	1.00
55	1	EA	1.00	1.00
56	1	EA	1.00	1.00
57	1	EA	1.00	1.00
58	1	EA	1.00	1.00
59	1	EA	1.00	1.00
60	1	EA	1.00	1.00
61	1	EA	1.00	1.00
62	1	EA	1.00	1.00
63	1	EA	1.00	1.00
64	1	EA	1.00	1.00
65	1	EA	1.00	1.00
66	1	EA	1.00	1.00
67	1	EA	1.00	1.00
68	1	EA	1.00	1.00
69	1	EA	1.00	1.00
70	1	EA	1.00	1.00
71	1	EA	1.00	1.00
72	1	EA	1.00	1.00
73	1	EA	1.00	1.00
74	1	EA	1.00	1.00
75	1	EA	1.00	1.00
76	1	EA	1.00	1.00
77	1	EA	1.00	1.00
78	1	EA	1.00	1.00
79	1	EA	1.00	1.00
80	1	EA	1.00	1.00
81	1	EA	1.00	1.00
82	1	EA	1.00	1.00
83	1	EA	1.00	1.00
84	1	EA	1.00	1.00
85	1	EA	1.00	1.00
86	1	EA	1.00	1.00
87	1	EA	1.00	1.00
88	1	EA	1.00	1.00
89	1	EA	1.00	1.00
90	1	EA	1.00	1.00
91	1	EA	1.00	1.00
92	1	EA	1.00	1.00
93	1	EA	1.00	1.00
94	1	EA	1.00	1.00
95	1	EA	1.00	1.00
96	1	EA	1.00	1.00
97	1	EA	1.00	1.00
98	1	EA	1.00	1.00
99	1	EA	1.00	1.00
100	1	EA	1.00	1.00

THIS PAGE IS NOT QUALITY REPRODUCIBLE
FROM COPY FILE

CONCRETE CONSTRUCTION-ROOFS

DOUBLE TEE



post & beam
upgrading

POSTS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber Posts		
2. Nails		
3. Hammer		
4. Saw		
5. Wedges		
6. Tape measure/yardstick, etc.		
7.		
8.		
9.		
10.		

details



CONCRETE CONSTRUCTION—ROOFS

WAFFLE SLAB



post upgrading

POSTS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber Posts		
2. Nails		
3. Hammer		
4. Saw		
5. Wedges		
6. Tape measure/yardstick, etc.		
7.		
8.		
9.		
10.		

details



CONCRETE CONSTRUCTION—ROOFS

FLAT SLAB



post upgrading

POSTS

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber Posts		
2. Nails		
3. Hammer		
4. Saw		
5. Wedges		
6. Tape measure/yardstick, etc.		
7.		
8.		
9.		
10.		

details



CONCRETE CONSTRUCTION—Roofs


FLAT PLATE

post upgrading


STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		






details



NAILING SCHEDULE	NAIL SIZE
TRANSVERSE (PERMANENT)	6d, 8d
1 x 6	6d, 10d, 12d
2 x 6	10d, 12d, 30d
3 x 6	12d, 30d, 60d
4 x 6	12d, 30d, 60d

* where b = width of brackets
 when b = 2" use 2 nails
 when b = 4" use 4 nails
 when b = 6" use 6 nails



THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO BDC

CONCRETE CONSTRUCTION-ROOFS

ONE-WAY JOIST

stud wall upgrading

POST & BEAM

RESOURCE LIST



Required

1. Timber (Posts)
2. Timber (Beams)
3. Nails
4. Hammer
5. Saw
6. Wedges
7. Tape measure/yardstick, etc.
8. _____
9. _____
10. _____

Quantity[illegible]

Available

[illegible]



NAME	DATE	TIME	TIME
1. 100	100	100	100
2. 100	100	100	100
3. 100	100	100	100
4. 100	100	100	100

Figure 1. The effect of the concentration of the *Agrobacterium* suspension on the transformation efficiency of *Agrobacterium* strains.

CONCRETE CONSTRUCTION-ROOFS


ONE-WAY JOIST

post & beam
upgrading


STUD WALL

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Studs & Plates)		
2. Bracing Material (Plywood Sheeting or nom. 1-in. Timber)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8. _____		
9. _____		
10. _____		



details



WALL TYPE (PERMANENT)	WALL TYPE
1. 12" x 12"	12" x 12"
2. 12" x 16"	12" x 16"
3. 12" x 20"	12" x 20"
4. 12" x 24"	12" x 24"
5. 12" x 28"	12" x 28"
6. 12" x 32"	12" x 32"
7. 12" x 36"	12" x 36"
8. 12" x 40"	12" x 40"
9. 12" x 44"	12" x 44"
10. 12" x 48"	12" x 48"
11. 12" x 52"	12" x 52"
12. 12" x 56"	12" x 56"
13. 12" x 60"	12" x 60"
14. 12" x 64"	12" x 64"
15. 12" x 68"	12" x 68"
16. 12" x 72"	12" x 72"
17. 12" x 76"	12" x 76"
18. 12" x 80"	12" x 80"
19. 12" x 84"	12" x 84"
20. 12" x 88"	12" x 88"
21. 12" x 92"	12" x 92"
22. 12" x 96"	12" x 96"
23. 12" x 100"	12" x 100"
24. 12" x 104"	12" x 104"
25. 12" x 108"	12" x 108"
26. 12" x 112"	12" x 112"
27. 12" x 116"	12" x 116"
28. 12" x 120"	12" x 120"
29. 12" x 124"	12" x 124"
30. 12" x 128"	12" x 128"
31. 12" x 132"	12" x 132"
32. 12" x 136"	12" x 136"
33. 12" x 140"	12" x 140"
34. 12" x 144"	12" x 144"
35. 12" x 148"	12" x 148"
36. 12" x 152"	12" x 152"
37. 12" x 156"	12" x 156"
38. 12" x 160"	12" x 160"
39. 12" x 164"	12" x 164"
40. 12" x 168"	12" x 168"
41. 12" x 172"	12" x 172"
42. 12" x 176"	12" x 176"
43. 12" x 180"	12" x 180"
44. 12" x 184"	12" x 184"
45. 12" x 188"	12" x 188"
46. 12" x 192"	12" x 192"
47. 12" x 196"	12" x 196"
48. 12" x 200"	12" x 200"
49. 12" x 204"	12" x 204"
50. 12" x 208"	12" x 208"
51. 12" x 212"	12" x 212"
52. 12" x 216"	12" x 216"
53. 12" x 220"	12" x 220"
54. 12" x 224"	12" x 224"
55. 12" x 228"	12" x 228"
56. 12" x 232"	12" x 232"
57. 12" x 236"	12" x 236"
58. 12" x 240"	12" x 240"
59. 12" x 244"	12" x 244"
60. 12" x 248"	12" x 248"
61. 12" x 252"	12" x 252"
62. 12" x 256"	12" x 256"
63. 12" x 260"	12" x 260"
64. 12" x 264"	12" x 264"
65. 12" x 268"	12" x 268"
66. 12" x 272"	12" x 272"
67. 12" x 276"	12" x 276"
68. 12" x 280"	12" x 280"
69. 12" x 284"	12" x 284"
70. 12" x 288"	12" x 288"
71. 12" x 292"	12" x 292"
72. 12" x 296"	12" x 296"
73. 12" x 300"	12" x 300"
74. 12" x 304"	12" x 304"
75. 12" x 308"	12" x 308"
76. 12" x 312"	12" x 312"
77. 12" x 316"	12" x 316"
78. 12" x 320"	12" x 320"
79. 12" x 324"	12" x 324"
80. 12" x 328"	12" x 328"
81. 12" x 332"	12" x 332"
82. 12" x 336"	12" x 336"
83. 12" x 340"	12" x 340"
84. 12" x 344"	12" x 344"
85. 12" x 348"	12" x 348"
86. 12" x 352"	12" x 352"
87. 12" x 356"	12" x 356"
88. 12" x 360"	12" x 360"
89. 12" x 364"	12" x 364"
90. 12" x 368"	12" x 368"
91. 12" x 372"	12" x 372"
92. 12" x 376"	12" x 376"
93. 12" x 380"	12" x 380"
94. 12" x 384"	12" x 384"
95. 12" x 388"	12" x 388"
96. 12" x 392"	12" x 392"
97. 12" x 396"	12" x 396"
98. 12" x 400"	12" x 400"
99. 12" x 404"	12" x 404"
100. 12" x 408"	12" x 408"
101. 12" x 412"	12" x 412"
102. 12" x 416"	12" x 416"
103. 12" x 420"	12" x 420"
104. 12" x 424"	12" x 424"
105. 12" x 428"	12" x 428"
106. 12" x 432"	12" x 432"
107. 12" x 436"	12" x 436"
108. 12" x 440"	12" x 440"
109. 12" x 444"	12" x 444"
110. 12" x 448"	12" x 448"
111. 12" x 452"	12" x 452"
112. 12" x 456"	12" x 456"
113. 12" x 460"	12" x 460"
114. 12" x 464"	12" x 464"
115. 12" x 468"	12" x 468"
116. 12" x 472"	12" x 472"
117. 12" x 476"	12" x 476"
118. 12" x 480"	12" x 480"
119. 12" x 484"	12" x 484"
120. 12" x 488"	12" x 488"
121. 12" x 492"	12" x 492"
122. 12" x 496"	12" x 496"
123. 12" x 500"	12" x 500"
124. 12" x 504"	12" x 504"
125. 12" x 508"	12" x 508"
126. 12" x 512"	12" x 512"
127. 12" x 516"	12" x 516"
128. 12" x 520"	12" x 520"
129. 12" x 524"	12" x 524"
130. 12" x 528"	12" x 528"
131. 12" x 532"	12" x 532"
132. 12" x 536"	12" x 536"
133. 12" x 540"	12" x 540"
134. 12" x 544"	12" x 544"
135. 12" x 548"	12" x 548"
136. 12" x 552"	12" x 552"
137. 12" x 556"	12" x 556"
138. 12" x 560"	12" x 560"
139. 12" x 564"	12" x 564"
140. 12" x 568"	12" x 568"
141. 12" x 572"	12" x 572"
142. 12" x 576"	12" x 576"
143. 12" x 580"	12" x 580"
144. 12" x 584"	12" x 584"
145. 12" x 588"	12" x 588"
146. 12" x 592"	12" x 592"
147. 12" x 596"	12" x 596"
148. 12" x 600"	12" x 600"
149. 12" x 604"	12" x 604"
150. 12" x 608"	12" x 608"
151. 12" x 612"	12" x 612"
152. 12" x 616"	12" x 616"
153. 12" x 620"	12" x 620"
154. 12" x 624"	12" x 624"
155. 12" x 628"	12" x 628"
156. 12" x 632"	12" x 632"
157. 12" x 636"	12" x 636"
158. 12" x 640"	12" x 640"
159. 12" x 644"	12" x 644"
160. 12" x 648"	12" x 648"
161. 12" x 652"	12" x 652"
162. 12" x 656"	12" x 656"
163. 12" x 660"	12" x 660"
164. 12" x 664"	12" x 664"
165. 12" x 668"	12" x 668"
166. 12" x 672"	12" x 672"
167. 12" x 676"	12" x 676"
168. 12" x 680"	12" x 680"
169. 12" x 684"	12" x 684"
170. 12" x 688"	12" x 688"
171. 12" x 692"	12" x 692"
172. 12" x 696"	12" x 696"
173. 12" x 700"	12" x 700"
174. 12" x 704"	12" x 704"
175. 12" x 708"	12" x 708"
176. 12" x 712"	12" x 712"
177. 12" x 716"	12" x 716"
178. 12" x 720"	12" x 720"
179. 12" x 724"	12" x 724"
180. 12" x 728"	12" x 728"
181. 12" x 732"	12" x 732"
182. 12" x 736"	12" x 736"
183. 12" x 740"	12" x 740"
184. 12" x 744"	12" x 744"
185. 12" x 748"	12" x 748"
186. 12" x 752"	12" x 752"
187. 12" x 756"	12" x 756"
188. 12" x 760"	12" x 760"
189. 12" x 764"	12" x 764"
190. 12" x 768"	12" x 768"
191. 12" x 772"	12" x 772"
192. 12" x 776"	12" x 776"
193. 12" x 780"	12" x 780"
194. 12" x 784"	12" x 784"
195. 12" x 788"	12" x 788"
196. 12" x 792"	12" x 792"
197. 12" x 796"	12" x 796"
198. 12" x 800"	12" x 800"
199. 12" x 804"	12" x 804"
200. 12" x 808"	12" x 808"
201. 12" x 812"	12" x 812"
202. 12" x 816"	12" x 816"
203. 12" x 820"	12" x 820"
204. 12" x 824"	12" x 824"
205. 12" x 828"	12" x 828"
206. 12" x 832"	12" x 832"
207. 12" x 836"	12" x 836"
208. 12" x 840"	12" x 840"
209. 12" x 844"	12" x 844"
210. 12" x 848"	12" x 848"
211. 12" x 852"	12" x 852"
212. 12" x 856"	12" x 856"
213. 12" x 860"	12" x 860"
214. 12" x 864"	12" x 864"
215. 12" x 868"	12" x 868"
216. 12" x 872"	12" x 872"
217. 12" x 876"	12" x 876"
218. 12" x 880"	12" x 880"
219. 12" x 884"	12" x 884"
220. 12" x 888"	12" x 888"
221. 12" x 892"	12" x 892"
222. 12" x 896"	12" x 896"
223. 12" x 900"	12" x 900"
224. 12" x 904"	12" x 904"
225. 12" x 908"	12" x 908"
226. 12" x 912"	12" x 912"
227. 12" x 916"	12" x 916"
228. 12" x 920"	12" x 920"
229. 12" x 924"	12" x 924"
230. 12" x 928"	12" x 928"
231. 12" x 932"	12" x 932"
232. 12" x 936"	12" x 936"
233. 12" x 940"	12" x 940"
234. 12" x 944"	12" x 944"
235. 12" x 948"	12" x 948"
236. 12" x 952"	12" x 952"
237. 12" x 956"	12" x 956"
238. 12" x 960"	12" x 960"
239. 12" x 964"	12" x 964"
240. 12" x 968"	12" x 968"
241. 12" x 972"	12" x 972"
242. 12" x 976"	12" x 976"
243. 12" x 980"	12" x 980"
244. 12" x 984"	12" x 984"
245. 12" x 988"	12" x 988"
246. 12" x 992"	12" x 992"
247. 12" x 996"	12" x 996"
248. 12" x 1000"	12" x 1000"
249. 12" x 1004"	12" x 1004"
250. 12" x 1008"	12" x 1008"
251. 12" x 1012"	12" x 1012"
252. 12" x 1016"	12" x 1016"
253. 12" x 1020"	12" x 1020"
254. 12" x 1024"	12" x 1024"
255. 12" x 1028"	12" x 1028"
256. 12" x 1032"	12" x 1032"
257. 12" x 1036"	12" x 1036"
258. 12" x 1040"	12" x 1040"
259. 12" x 1044"	12" x 1044"
260. 12" x 1048"	12" x 1048"
261. 12" x 1052"	12" x 1052"
262. 12" x 1056"	12" x 1056"
263. 12" x 1060"	12" x 1060"
264. 12" x 1064"	12" x 1064"
265. 12" x 1068"	12" x 1068"
266. 12" x 1072"	12" x 1072"
267. 12" x 1076"	12" x 1076"
268. 12" x 1080"	12" x 1080"
269. 12" x 1084"	12" x 1084"
270. 12" x 1088"	12" x 1088"
271. 12" x 1092"	12" x 1092"
272. 12" x 1096"	12" x 1096"
273. 12" x 1100"	12" x 1100"
274. 12" x 1104"	12" x 1104"
275. 12" x 1108"	12" x 1108"
276. 12" x 1112"	12" x 1112"
277. 12" x 1116"	12" x 1116"
278. 12" x 1120"	12" x 1120"
279. 12" x 1124"	12" x 1124"
280. 12" x 1128"	12" x 1128"
281. 12" x 1132"	12" x 1132"
282. 12" x 1136"	12" x 1136"
283. 12" x 1140"	12" x 1140"
284. 12" x 1144"	12" x 1144"
285. 12" x 1148"	12" x 1148"
286. 12" x 1152"	12" x 1152"
287. 12" x 1156"	12" x 1156"
288. 12" x 1160"	12" x 1160"
289. 12" x 1164"	12" x 1164"
290. 12" x 1168"	12" x 1168"
291. 12" x 1172"	12" x 1172"
292. 12" x 1176"	12" x 1176"
293. 12" x 1180"	12" x 1180"
294. 12" x 1184"	12" x 1184"
295. 12" x 1188"	12" x 1188"
296. 12" x 1192"	12" x 1192"
297. 12" x 1196"	12" x 1196"
298. 12" x 1200"	12" x 1200"
299. 12" x 1204"	12" x 1204"
300. 12" x 1208"	12" x 1208"
301. 12" x 1212"	12" x 1212"
302. 12" x 1216"	12" x 1216"
303. 12" x 1220"	12" x 1220"
304. 12" x 1224"	12" x 1224"
305. 12" x 1228"	12" x 1228"
306. 12" x 1232"	12" x 1232"
307. 12" x 1236"	12" x 1236"
308. 12" x 1240"	12" x 1240"
309. 12" x 1244"	12" x 1244"
310. 12" x 1248"	12" x 1248"
311. 12" x 1252"	12" x 1252"
312. 12" x 1256"	12" x 1256"
313. 12" x 1260"	12" x 1260"
314. 12" x 1264"	12" x 1264"
315. 12" x 1268"	12" x 1268"
316. 12" x 1272"	12" x 1272"
317. 12" x 1276"	12" x 1276"
318. 12" x 1280"	12" x 1280"
319. 12" x 1284"	12" x 1284"
320. 12" x 1288"	12" x 1288"
321. 12" x 1292"	12" x 1292"
322. 12" x 1296"	12" x 1296"
323. 12" x 1300"	12" x 1300"
324. 12" x 1304"	12" x 1304"
325. 12" x 1308"	12" x 1308"
326. 12" x 1312"	12" x 1312"
327. 12" x 1316"	12" x 1316"
328. 12" x 1320"	12" x 1320"
329. 12" x 1324"	12" x

AD-A085 024

SCIENTIFIC SERVICE INC REDWOOD CITY CA
SHELTER UPGRADING MANUAL: HOST AREA SHELTERS. (U)
MAR 80 C WILTON, B L GABRIELSEN, R S TANSLEY
SSI-7815-8

F/6 13/13

DCPA01-78-C-0215


NL

UNCLASSIFIED

3143
90A
JAN 82



END
DATE
FILMED
7-80
DTIC




POST & BEAM

RESOURCE LIST

<u>Required</u>	<u>Quantity</u>	<u>Available</u>
1. Timber (Posts)		
2. Timber (Beams)		
3. Nails		
4. Hammer		
5. Saw		
6. Wedges		
7. Tape measure/yardstick, etc.		
8.		
9.		
10.		

details



NAILING	DETAIL	SPACING
BEAM	SECTION	DETAIL
1 x 6	6d	12 in.
2 x 6	6d	12 in.
3 x 6	6d	12 in.
4 x 6	6d	12 in.
6 x 6	6d	12 in.
8 x 6	6d	12 in.
10 x 6	6d	12 in.
12 x 6	6d	12 in.
14 x 6	6d	12 in.
16 x 6	6d	12 in.
18 x 6	6d	12 in.
20 x 6	6d	12 in.
22 x 6	6d	12 in.
24 x 6	6d	12 in.
26 x 6	6d	12 in.
28 x 6	6d	12 in.
30 x 6	6d	12 in.
32 x 6	6d	12 in.
34 x 6	6d	12 in.
36 x 6	6d	12 in.
38 x 6	6d	12 in.
40 x 6	6d	12 in.
42 x 6	6d	12 in.
44 x 6	6d	12 in.
46 x 6	6d	12 in.
48 x 6	6d	12 in.
50 x 6	6d	12 in.
52 x 6	6d	12 in.
54 x 6	6d	12 in.
56 x 6	6d	12 in.
58 x 6	6d	12 in.
60 x 6	6d	12 in.
62 x 6	6d	12 in.
64 x 6	6d	12 in.
66 x 6	6d	12 in.
68 x 6	6d	12 in.
70 x 6	6d	12 in.
72 x 6	6d	12 in.
74 x 6	6d	12 in.
76 x 6	6d	12 in.
78 x 6	6d	12 in.
80 x 6	6d	12 in.
82 x 6	6d	12 in.
84 x 6	6d	12 in.
86 x 6	6d	12 in.
88 x 6	6d	12 in.
90 x 6	6d	12 in.
92 x 6	6d	12 in.
94 x 6	6d	12 in.
96 x 6	6d	12 in.
98 x 6	6d	12 in.
100 x 6	6d	12 in.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

CONCRETE CONSTRUCTION--ROOFS HOLLOW-CORE

post & beam
upgrading

SECTION 7- Worksheets


SECTION 7

WORKSHEETS

INDEX

	<u>Page</u>
WORKSHEET A - Stud Wall Upgrading	7-1
WORKSHEET B - Post and Beam Upgrading	7-2
WORKSHEET C - King Post Truss Upgrading	7-3
WORKSHEET D - Flange Upgrading	7-4
WORKSHEET E - Boxed Beam Upgrading	7-5
WORKSHEET F - Post Upgrading	7-6
WORKSHEET G - Beam Shoring	7-7

WORKSHEET A stud wall upgrading



L _____ W _____ H _____

1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided above. These dimensions need not be exact - the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.

2. Sketch in the figure above the intended location of the stud wall(s). If one wall is used, it should be located at midspan along dashed line (W/2) and if two are used, at 1/3 span (W/3) along dotted lines. The wall (s) should be continuous the full length (L) of the area.

3. Determine the distance (X) from the stud wall to the adjacent support (wall, beam, other stud wall, etc.).

X = _____ ft

4. With (X) and (H) from above, go to Chart A, page 8-1, Section 8, to determine the timber size required; enter

Chart A from left with (X) and read over to ceiling height (H). Read above intersection point to find the size of studs and spacing that may be used.

Stud Size _____ in. by _____ in.
at _____ in. on center.

5. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

Studs _____ in. by _____ in.

H _____ ft x L _____ ft x 12 _____ in. ft
_____ in. on center

Top Plates (same size as studs,
two required)

L _____ ft x 2 = _____ lin. ft

Bottom Plate (same size as
studs, one required)


L _____ ft x 1 = _____ lin. ft

Total Timber Required = _____ lin. ft

Note: If two walls are used, double the above timber requirement. Enter size and linear feet of timber required on the Resources List.

6. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 - Beam Shoring, to determine post shores required.

WORKSHEET B post & beam upgrading



1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided above. These dimensions need not be exact - the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.

2. Sketch in the figure above the intended location of the timber beams and locate the timber posts required to support them. If one line of beams is used, it should be located at midspan (W/2) along dashed line, and if two are used, at 1/3 span (W/3) along dotted lines. The line(s) of posts and beams should be continuous the full length (L) of the area.

3. Determine the distance (X) from the beam line to the adjacent support (wall, beam, etc.).

X = _____ ft

Determine the distance between the posts (Y).

Y = _____ ft

Multiply X x Y = _____ sq ft supported area.

4. With the supported area and (H) from above, go to Chart B, page 8-2, Section 8, to determine the timber post size required. Enter the chart from the left with the supported area and read over to ceiling height. Read above the intersection point to find the size of timber posts that may be used.

Post Size _____ in. by _____ in.

5. To determine the required beam size, go to Chart C, page 8-3, Section 8. Enter chart from left with the distance between supports (X) and read over to the distance between posts, or span (Y). Read above intersection point to find the size of timber beams that may be used.

Beam Size _____ in. by _____ in.

6. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

Posts _____ in. by _____ in.

No. of Posts _____ x H _____ ft = _____ lin. ft

Beams _____ in. by _____ in.


L = _____ lin. ft

Total Timber Required = _____ lin. ft

Note: If two lines of shoring are used, double the above timber requirement. Enter size and linear feet of timber required on Resources List.

7. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 - Beam Shoring, to determine post shores required.

WORKSHEET C king post truss upgrading



1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided above. These dimensions need not be exact - the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.

2. The material requirements for King Post Truss upgrading vary greatly with the type of system to be upgraded. The details, shown with each of the individual sketches depicting the upgrading scheme, should be examined closely. Various methods of attachment and installation are suggested for each scheme. Once a scheme has been selected, identification and a count of all the anchors and attachments required should be made, and this information entered on the Resources List.


3. To determine the amount of cable required, count the number of joists and/or beams to be upgraded (N) and multiply by their length (W). Two feet should be added to each member length to account for end anchorages and initial cable slack, which is desired for ease in installation. Cable requirements may then be determined as follows:

$$(W + 2) \text{ ft} \times N = \text{lin. ft}$$

Note: If two cables are required per joist/beam (see sketch of upgrading scheme), double the above requirement. Enter the linear feet of cable required on Resources List.

4. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 - Beam Shoring, to determine post shores required.

WORKSHEET D flange upgrading




1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided below illustration. These dimensions need not be exact — the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.
2. Determine the number of joists in the intended shelter area (N).
3. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

$$N \quad \text{ } \times \text{ } W \quad \text{ } \text{ft} = \quad \text{ } \text{lin. ft}$$

Enter the linear feet of timber required on Resources List.
4. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 — Beam Shoring, to determine post shores required.

WORKSHEET E boxed beam upgrading



1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided below illustration. These dimensions need not be exact — the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.


2. Plywood Requirements: With the above information, a rough estimate of the plywood required for the upgrading may be made.

$$W \text{ } \underline{\hspace{1cm}} \text{ ft} \times L \text{ } \underline{\hspace{1cm}} \text{ ft} \times 2 = \underline{\hspace{1cm}} \text{ sq ft}$$

Enter the square feet of plywood required on Resources List.

3. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 — Beam shoring, to determine post shores required.

WORKSHEET F post upgrading



L _____ W _____ H _____

1. Measure the intended shelter area. Fill in the length (L), width (W), and height (H) of the area in the spaces provided above. These dimensions need not be exact — the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.

2. Sketch in location of timber posts on illustration symmetrically throughout the shelter area. The posts would be located at the intersections of the dashed or dotted lines as follows: midspan, center dashed lines (W/2 and L/2); 1/3 span, dotted lines (W/3 and L/3); 1/4 span, all dashed lines (W/4 and L/4). The posts should also be located at the intersections of these lines with the line between existing columns.

3. Determine the supported area of each post by multiplying the distance between posts in each direction (X and Y). X would be equal to either W/2, W/3 or W/4, and Y would be equal to L/2, L/3 or L/4, depending on the post locations. Therefore:

X _____ ft x Y _____ ft = _____ sq ft supported area

4. With the supported area and (H) from above, go to Chart D, page 8-4, Section 8, to determine the timber post size required. Enter the chart from left with the supported area and read over to ceiling height. Read above the intersection point to find the size of timber post that may be used.

Post Size _____ in. by _____ in.

5. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.


Posts _____ in. by _____ in.

No. of Posts _____ x H _____ ft = _____ lin. ft

Enter size and linear feet of timber required on Resources List.

6. If existing ceiling support(s) are beams in lieu of bearing walls, additional shoring should be provided. Use Worksheet G, page 7-7, Section 7 — Beam Shoring, to determine post shores required.

WORKSHEET G beam shoring



L _____ W₁ _____ H _____
W₂ _____

1. This Worksheet is to be used when the existing ceiling support(s) are beams in lieu of bearing walls. These beams require upgrading with timber posts.
2. Measure the intended shelter area. Fill in the length (L), widths (W₁ and W₂), and height (H) of the area in the spaces provided above. These dimensions need not be exact - the length and width to the nearest foot and the height to the nearest 6 in. is sufficient.
3. Sketch in the figure above the intended location of the posts along the existing beam. They should be located symmetrically at L/2, L/3, or L/4.

4. Determine the distance between the posts (Y).

Y = _____ ft

Calculate (X).

$$\frac{W_1 + W_2}{2} = X = \text{_____ ft}$$

Multiply X x Y = _____ sq ft supported area

5. With the supported area and (H) from above, go to either Chart B, page 8-2, or Chart D, page 8-4, Section 8, to determine the timber post size required. Use Chart B if the post is supporting a timber beam and Chart D if the post is supporting a beam other than timber (steel, concrete, etc.). Enter the appropriate chart from the left with the supported area and read over to ceiling height. Read above the intersection point to find the size of timber post that may be used.

Post Size _____ in. by _____ in.

6. Timber Requirements: With the above information, a rough estimate may be made of the timber required for the upgrading.

Post _____ in. by _____ in.

No. of Posts _____ x H _____ ft = _____ lin. ft

Enter size and linear feet of timber required on Resources List.


SECTION 8 • Charts


SECTION 8

CHARTS

INDEX

CHART A - Stud Wall Data	8-1
CHART B - Timber Post Data (with Timber Beam Data only)	8-2
CHART C - Timber Beam Data	8-3
CHART D - Timber Post Data	8-4







NOTE:
USE THIS CHART WHEN
SUPPORTING TIMBER BEAM

TIMBER POST DATA (WITH TIMBER BEAM DATA ONLY)

TIMBER BEAM DATA





NOTE:
USE THIS CHART WHEN
SUPPORTING BEAM OTHER
THAN TIMBER (STEEL, CONCRETE, ETC.)

TIMBER POST DATA

APPENDIX A- Evaluation of
Potential Shelter
Facilities

APPENDIX A
EVALUATION OF POTENTIAL SHELTER FACILITIES

Appendix A
EVALUATION OF POTENTIAL SHELTER FACILITIES

INTRODUCTION

Section 2 described a method for evaluating potential shelter facilities based on "intended use", or more specifically, the use for which the structure was initially designed. The objective of this section is to further assist in this evaluation by outlining some of the particular structural characteristics of building systems and materials that are important factors in arriving at a valid determination of the usefulness of the structure as a shelter.

INTENDED USE

Unfortunately, the "intended use" of a floor or roof is not always easily discernible, particularly in older buildings. Some residential homes (light) have been converted to restaurants (medium); warehouses (heavy) are now used as retail stores (medium); etc. Accordingly, it is important that "intended use" not be confused with "present use". The potential shelter facility may be better or worse than its "present use" indicates. Obviously, judgment on whether the system is light, medium or heavy should always be made on the conservative side if the facts on the building's history are not known or obtainable.

STRUCTURAL INTEGRITY

Once a potential shelter is selected, a reasonably thorough inspection should be conducted of the structural supporting members (deck/slab, beams, girders, columns, and walls). If the shelter is to perform up to the anticipated survival rating, it must not contain any major structural defects. All structures have built-in safety factors in both the materials and the expected loading. Accordingly, a structure may appear to be in fairly good shape and be serviceable, but, because of structural

defects, it may have lost the excess safety provided by these built-in factors. If this is the case, the use of this particular structure as a shelter would be questionable, and, at the very least, it should have a downgraded survival rating.

While it would be advantageous to have such an inspection conducted by individuals with expertise in building design, such as engineers or architects, this will seldom be possible. It is believed that an individual without such expertise, provided with some basic guidelines, small hand tools, and exercising reasonable judgment, can conduct an inspection that will be valuable in determining the structural integrity of a potential shelter. The following parts of this section outline, in a very basic way, the procedures for such an inspection, list the most likely areas for inspection, and assist in the evaluation of the structure for use as a shelter.

WOOD CONSTRUCTION

Light and medium floors would essentially be similar types of construction — timber joists supported on either solid concrete or concrete block walls, or steel or timber beams supported by steel or timber columns. We will confine this discussion to all timber construction since steel construction will be considered later in this section.

Heavy timber construction would usually be found in older structures as it is not presently in common usage. It would most generally consist of heavy timber beams, girders, and columns supporting heavy plank deck and flooring. The column/girder and beam/girder connections are usually heavy cast iron or steel seats and/or brackets.

The principal problems to be considered in connection with timber structures are decay, insect attack, excessive deflection, checking, splitting due to shrinkage of the timbers in place, and deterioration of the connection hardware. These conditions can all be checked visually with the aid of a flashlight and an ice pick or knife. Decay, insect attack, and shrinkage splitting, unless extremely

excessive (25% of individual timber destroyed), would not be a determining factor in shelter evaluation. On the other hand, excessive deflection and deteriorated connection hardware are problems that could cause premature collapse during use as a shelter.

Joists or timber beams that are bowing downward in excess of $\frac{1}{4}$ in. per 3 ft of length are certainly not performing as designed, and downgrading of the shelter area should be considered if this condition is found.

Probably the most important areas to be considered for inspection are bearing and connections. The ends of the joists should be examined for adequate bearing (2 in. minimum). The timber beams should be bearing on the walls and/or columns a minimum of 3 in. The connections between the beams and columns should be secure and intact. The column should be plumb (vertical) and its base should be firmly attached to the floor with no evidence of excessive movement.

All of the above inspections may be conducted visually. Generally, what is looked for is any movement of the structure since construction. Movement of the structure, whether caused by foundation settlement, timber shrinkage, or other causes, can cause loss of bearing and connection distress. If such conditions are noted, downgrading of the shelter should be considered.

STEEL CONSTRUCTION

Light steel construction generally consists of steel bar joists (trusses) supporting metal deck or plywood topped with concrete fill or insulation board, supported on steel beams and/or concrete or block walls. The columns are usually steel pipe or tube.

Heavy steel construction consists of steel columns, girders and beams (usually I-shaped sections), and a supporting metal deck topped with structural concrete. The member connections are welded, riveted, or bolted.

Steel bar joists should be inspected thoroughly since the nature of their design requires proper initial installation as well as a future absence of even minor defects in order to assure satisfactory performance. An inspection of a bar joist floor or roof should begin with an overall look at the system. Are the bottom chords even and level with respect to each other, not one higher or lower than the other? The joists should all be in a vertical plane, not leaning to one side or the other. They should not be bowed horizontally. The joists should have lateral bridging, i.e., steel bars or angles located near the top and bottom of the joists, running perpendicular to and connecting the joists to each other by welding. The joists should have no sharp bends or "kinks" in them — such as could be caused by impact by a piece of equipment from below.

The second phase of the inspection should be done with a flashlight and scraper or screwdriver. Each end of each joist should be checked to assure that it is securely connected to the walls or beams. This connection should be accomplished with welds or embedded bolts (embedded in the concrete wall) welded to the joists. The webs (the diagonals running between the top and bottom chords) should be welded at each point of contact to the chords. It may be necessary to chip or scrape away dirt or corrosion in order to be able to observe these conditions. If only several welds are broken, or one joist appears bowed or deflected, it may be possible to make expedient repairs by rewelding or by double shoring the defective joist. If the defects are prevalent, downgrading the shelter area should be considered.

The primary deterioration of heavy steel structures is caused by corrosion, loosening of connections, foundation settlement, fatigue, and impact. Again, a cursory inspection looking for very badly deflected, bowed, or bent beams, girders, or columns would be in order. A closer examination with a flashlight and a scraper may reveal fatigue cracks or waviness in the flanges or webs. Corroded areas should be scraped to determine how deep the corrosion has penetrated. A hammer should be used if necessary, to remove loose material and assure penetration to "good" steel. Corrosion has been known to completely deteriorate quite large steel members. If the corrosion is not excessive (over 25% of the original thickness) nor widespread (over 10% of the total structure), and if the cracks found are "hairline" in width, short

and only several per member, the structure could be used as a potential shelter.

The final, and most critical, inspection is that of the connections. It should be determined that the welds, if any, are not cracked or corroded through. If bolts or rivets are present, they should be in place, not loose and not exhibit severe corrosion. Gusset plates and beam seats should be intact, not twisted, and secure to each member they are intended to hold together. The column should be plumb and connected top and bottom.

Obviously, one or two bolts missing or light corrosion is acceptable. However, it should be mentioned that only one severely deteriorated connection in this type of structure could cause collapse when used as a shelter.

CONCRETE CONSTRUCTION

Concrete construction is one of the more difficult types of construction to inspect visually since one of the primary structural components, the reinforcing steel or strands, is completely hidden from view. Conversely, if severe structural problems do exist, they are usually readily apparent to the observer.

Three basic visual symptoms of distress in concrete structures should be investigated: cracking, spalling, and disintegration. Although all of these conditions, particularly in their later stages, are unsightly, they are not necessarily structurally significant, and many times can be neglected in the evaluation for shelter use.

In general, cracking in concrete is an inherent characteristic of the material. Hairline cracks caused by shrinkage, and surface craze-cracking, usually caused during the finishing operations, are of no structural concern.

Spalling and deterioration, unless reducing the section (size) of the beam or slab by more than 10%, with the exceptions mentioned later, would not be reason for downgrading the shelter. This would be true even if this condition exposed the reinforcing steel or prestressing strand to some degree. The steel should, however, then be checked for corrosion. A good tool for determining extent of deterioration is a hammer. Sound concrete has quite a different "ring" to it than does deteriorated concrete, when lightly tapped with a hammer.

Conditions that should be checked, and if found to exist would be a basis for considering downgrading the shelter, are as follows: Cracks in slab floors (flat slabs, flat plates, and waffle slabs) 1/8 in. or wider around the periphery of the column or drop panel location; vertical or diagonal cracks, 1/8 in. or wider, at or near the supports of the beams, double or single stemmed units and prestressed slabs; excessive deflection in any member or slab (over 1/4 in. per 3 ft of length); cracks in bottom of slabs or members near midspan greater than 1/4 in. wide and extending up into the member more than 60% of its overall depth; and bearing less than 2 in. at the ends of precast members.

Although it is not possible to do expedient repair on cracks in concrete — this should be done by experts — some of the above problems can be negated by use of additional shoring under those members adjacent to the distressed areas.

WALLS

Walls will generally be poured-in-place concrete, precast concrete panels, or concrete block. Inspection of walls should be conducted with a flashlight and a light hammer.

Poured-in-place and concrete block walls are usually 8 to 12 in. thick and are solid concrete or individual hollow-core concrete blocks, with or without the cores filled with grout, mortared in place. These wall types should be checked for severe cracking and vertical and horizontal displacement. Most walls will have inherent cracking, and cracks up to 1/8 in. wide are acceptable provided the displacement

is minimal. If the wall is 8 ft high, it should not be leaning in or out more than a maximum of 1 in.

Precast concrete panels are usually installed as individual panels 8 to 12 ft wide and welded together at each joint. Again, the panels should be checked for severe cracking and displacement. An attempt should be made, if possible, to locate the welds and make sure that they are intact. However, this can sometimes prove difficult. If the panels are true and flush with each other and there has been no vertical displacement, the welds could be considered secure. Again, they should not be out of vertical alignment more than 1 in. in 8 ft.

SUMMATION

Much information may be obtained about the structural integrity of a potential shelter with the use of small tools, by picking, scraping, and rubbing. However, nothing is more valuable in making an evaluation than observation. It must be assumed, for our purposes, that the original design and construction was proper and within the accepted code limits. Accordingly, what you are attempting to ascertain is whether, during the life of the structure, changes have occurred which have altered its structural usefulness as a potential shelter. Observe the cracks: Are they "new" cracks, is the wood fresh and new looking inside the crack, is the exposed steel in a crack bright and shiny? These observations may indicate whether the apparent distress is dormant or active, and if active, a cause for concern.

If the beams have shifted on their supports, you should be able to observe their original location, and estimate the degree of displacement.

Observation should be made of rivets or bolts out of line and twisted or bent bolts and nails, all indicating movement of the structure. Again, if the structure has apparently performed adequately for a considerable length of time since the movement occurred, downgrading may not be necessary.

In addition, observations should be made, and consideration taken, of all structural modifications that appear to have been made after the original structure was completed: doors or windows sawed or cut through walls; ducts, pipes, or wiring passing through holes cut in joists or beams; added flooring of concrete or bricks; or heavy walls of brick or block added on the floor above. Some of these conditions may not have been contemplated in the original design, and accordingly, the structure may require downgrading.

APPENDIX B - Closures

APPENDIX B

CLOSURES

Appendix B CLOSURES




It is probable that the majority of shelter spaces will need some form of closure. For example, a basement that has had the floor upgraded will probably have a stairway, windows, doors, ventilation ducts, access openings, etc. This section of the manual describes several methods of closing off such typical openings in the walls or ceilings.

Openings can be bridged by use of a number of readily available materials, such as wood, steel, or concrete. Examples of wood that may be used are fence posts, cut-up power poles, railroad ties, solid doors, and standard beams and plank pieces. Examples of concrete are sidewalk slab sections and curb or gutter pieces; and of steel, plate would appear to be the most practical from a handling and placing standpoint, but steel rolled sections could also be used. Additional materials that may be used to close openings are bags or oil or paper drums filled with sand or earth, broken concrete, bricks, or concrete blocks. Table B-1 contains a list of some of the materials that might be considered for use in closing openings.


With the wood and concrete categories there are material differences, which affect their strength. Wood fence posts, power poles, or railroad ties could be badly splintered or rotted in the center. Wood beams and planks could also be badly splintered. Generally, "poor" timber is "utility" grade when new, as well as older material that now has loose knots, or holes where the knots have fallen out. Poor timber may also have many checks, shakes, and splits. These features are illustrated in Fig. B-1. The concrete sidewalk slab and curb sections usually contain minimum or no reinforcing. These sections should be inspected for any significant cracking, which could impair their intended use.

Table B-1
CLOSURE MATERIALS

Steel doors	* Filled sandbags
Wood doors (solid)	* Filled paper bags
Toilet doors and partitions	* Filled paper boxes
Tree trunks and limbs	* Filled plastic garbage cans
Steel cover plates	Brick or concrete block
Desk and table tops	* Filled oil or paper drums
Railroad ties	Broken concrete
Plywood	
Concrete slabs (sidewalks, etc.)	*filled with sand or earth
Wood, steel, or concrete fence posts	
Telephone or power poles	



ROTTED TIES OR POSTS



SPLINTERED POSTS / POLES / TIES

Fig. B-1. Factors Affecting Wood Strength.

The chart shown in Fig. B-2 indicates the maximum opening width that may be spanned without intermediate support for various materials. This chart can be used in several ways; (1) Enter the chart with the minimum opening width and list the type and thicknesses of the materials that would be required; a survey of the available resources could then be made in order to narrow the list to those most available or obtainable. (2) Enter the chart with a known available resource and determine the width of closure that this material will accommodate; this procedure will indicate if a further search for other resources will be required.

Example 1 --- Assume there are two openings: one, 18 in. in diameter and one, 48 in. by 54 in.

The shortest dimensions are 18 in. and 48 in., respectively. Entering the chart from the left with these dimensions (see Fig. B-3) yields the following list of materials:

<u>18 - in. Diameter</u>		<u>48 in. x 54 in.</u>	
1-in. wood post		3-in. wood post	
1/8-in. steel plate		3/8-in. steel plate	
1-in. timber (good or poor)		2-in. timber (good)	
2-in. concrete sidewalk slab		3-in. timber (poor)	
4-in. concrete curb/gutter		6-in. concrete sidewalk slab	
		8-in. concrete curb/gutter	

With these lists, check available resources.

Example 2 --- Assume that you have a large quantity of 2-in.-thick wood fence material, which you consider to be in "poor" condition (see Fig. B-1). Entering the chart from the bottom at 2-inch Poor Timber shows that the maximum opening that can be closed with this material is approximately 36 inches. If you have openings larger than that, proceed as in Example 1 for these larger openings, and develop a list of required resources.




Fig. B-2. Material Thicknesses Required to Close Various Openings.




Fig. B-3. Material Thickness Chart as used in Example No. 1.

It should be remembered that the closed openings also require radiation protection. The chart on page 2-2, Section 2, indicates that the thicknesses of materials required to achieve various protection factors (P_f). One straightforward method is, of course, placing earth over the closed opening if it is horizontal, or piling earth against the closure if it is vertical. This, however, might prove to be difficult without a large number of personnel or earth-moving equipment, particularly over a basement floor enclosed by a structure on all sides. One expedient method of accomplishing this task is to place the earth (or sand or gravel) in containers such as sandbags, paper bags, cardboard boxes, plastic garbage cans, or oil or cardboard drums.

Figs. B-4, B-5, and B-6 show examples of suggested methods for closing several types of openings.





Fig. B-4. Window Closures.





Fig. B-5. Stair and Door Closures.




Fig. B-6. Door and Small Opening Closures.

APPENDIX C- Shoring
Alternative
Systems

APPENDIX C

ALTERNATIVE SHORING SYSTEMS

Appendix C

ALTERNATIVE SHORING SYSTEMS

In addition to the materials previously described and illustrated, there are other shoring materials that may be locally available and equally useful. Some construction projects or contracting yards may have shores or scaffold frames on hand. Shores are single post supports, while scaffolds are metal frames, each looking like an inverted "U" with cross bars. Shores can be either metal or wood. These types of shores are very useful in that they are generally designed for fast removal and erection and are adjustable to a variety of lengths. In addition to these commercial shores, there exist other available materials that may be utilized. Telephone posts cut to length, railroad ties, tree trunks and large limbs, and wood fence posts are examples. Steel pipe, steel fence posts, and structural steel sections (I-beams, channels, angles, tubes, etc.) may also be utilized. Table C-1 lists the relative strengths of some of these examples as compared to the dimensional timber posts of Charts B and D, pages 8-2 and 8-4, Section 8, for a fixed shoring height of 8 ft.

Important points to remember in setting any type of shore are that, if the shore is being used in a vertical position, set it as vertical as possible as observed from two different directions, and center the shore directly under the beam that is being supported. Also, always clear an area where the shore stands. Any type of wood or trash, etc., on a concrete floor, for example, may cause the shore to slide. When these shores rest on the ground, there should be a piece of plywood or lumber between the bottom and the ground to spread the load. Scaffold frames are limited to locations where they can be hauled in and set up without clearance problems.


Several types of shoring are illustrated in Figs. C-1 and C-2; the sequence for setting the wood post shore is shown in Fig. C-3; and suggested applications of both shores and scaffolding are shown in Fig. C-4.

Table C-1

EXAMPLES OF MINIMUM SIZES OF ALTERNATIVE TYPES OF SHORES, 8 FT HIGH,
AND THEIR RELATIONSHIP TO TIMBER POST CHARTS IN SECTION 8

Type of Alternative Shore	Minimum Size	Equivalent on Charts B & D	Remarks
<u>Commercial Shores</u>			
Wood or steel*	—	4" x 4"	Wood or steel posts, scaffolds
<u>Wood</u>			
Telephone post	10" dia.	8" x 10"	Good condition
Railroad tie	7" x 7"	6" x 8"	Good condition
Tree trunks or limbs	5" dia.	4" x 4"	Straight section
Fence post	4" x 4"	4" x 4"	Good condition
<u>Structural Steel*</u>			
Standard pipe	3½" dia.	4" x 4"	¼-in. thick wall
I-beams	S 6 x 17.25	4" x 4"	6" deep, 3-3/8" wide
Square tubes	TS 4 x 4 x .25	4" x 4"	
Rectangular tubes	TS 5 x 3 x .25	4" x 4"	
Angles, equal legs	L 5 x 5-5/16	4" x 4"	
Angles, unequal legs	L 6 x 4 x ½	4" x 4"	
Channels	C 15 x 33.9	4" x 4"	

* When supporting timber beam with steel shore, plates should be used between top of shore and beam to distribute loads.



All wood post shore capable of adjusting to a great variety of heights.

Wood post snore with metal base adjustment, which can be adjusted only a small amount.

Fig. C-1.





Fig. C-2. Steel Shoring.



- 1) Take post in retracted position and set vertically under point to be shored.
- 2) Shove post up to beam.
- 3) While post is held up, strike clamps with a hammer to set and thus secure sliding post.
- 4) Drive nails to wedge clamps so they can't move. Note: Floor post side clamps on the floor post are set with nails prior to Step 1.

Fig. C-3 Sequence for Setting All Wood Post Shore.




Fig. C-4. Applications of Wood Post Shores and Scaffolds.

DISTRIBUTION LIST

Federal Emergency Management Agency
Mitigation and Research
Attn: Administrative Officer
Washington, D.C. 20472 (60)

Assistant Secretary of the Army (R&D)
Attn: Assistant for Research
Washington, D.C. 20301

Chief of Naval Research
Washington, D.C. 20360

Commander, Naval Supply Systems
Command (0421G)
Department of the Navy
Washington, D.C. 20376

Commander
Naval Facilities Engineering Command
Research and Development (Code 0322C)
Department of the Navy
Washington, D.C. 20390

Defense Documentation Center
Cameron Station
Alexandria, VA 22314 (12)

Civil Defense Research Project
Oak Ridge National Laboratory
Attn: Librarian
P.O. Box X
Oak Ridge, TN 37830

U.S. Naval Civil Engineering Laboratory
Attn: Document Library
Port Hueneme, CA 93041

Air Force Special Weapons Laboratory
Attn: Technical Library
Kirtland Air Force Base
Albuquerque, NM 87117

AFWL/Civil Engineering Division
Kirtland AFB, New Mexico 87117

Civil Engineering Center/AF/PRECET
Wright-Patterson AFB, Ohio 45433

Chief of Engineers
Department of the Army
Attn: ENGME-RF
Washington, D.C. 20314

Office of the Chief of Engineers
Department of the Army
Attn: Mr. Tomassoni
Washington, D.C. 20314

Director, U.S. Army Engineer
Waterways Experiment Station
P.O. Box 631
Vicksburg, MS 39180

Director, U.S. Army Engineer
Waterways Experiment Station
Nuclear Weapons Effects Branch
P.O. Box 631
Vicksburg, MS 39180

Director, Defense Nuclear Agency
Attn: Technical Library
Washington, D.C. 20305

Director, Defense Nuclear Agency
Attn: Mr. Tom Kennedy
Washington, D.C. 20305

Director, U.S. Army Ballistic
Research Laboratory
Attn: Document Library
Aberdeen Proving Ground, MD 21005

Director, U.S. Army Ballistic
Research Laboratory
Attn: Mr. William Taylor
Aberdeen Proving Ground, MD 21005

Aghabian Associates
250 N. Nash Street
El Segundo, CA 90245

The Rand Corporation
1700 Main Street
Santa Monica, CA 90401

The Dikewood Corporation
1009 Bradbury Drive, S.E.
University Research Park
Albuquerque, NM 87106

Mr. J.W. Foss
Supervisor, Buildings Studies Group
Bell Telephone Laboratories, Inc.
Whippany Road
Whippany, NJ 07981

Dr. William J. Hall
University of Illinois
111 Talbot Laboratory
Urbana, IL 61801

Mr. Samuel Kramer, Chief
Office of Federal Building Technology
Center FOB Building Technology
National Bureau of Standards
Washington, D.C. 20234

Mr. Anatole Longinow
IIT Research Institute
10 West 35th Street
Chicago, IL 60616

Dr. Stanley B. Martin
Stanford Research Institute
333 Ravenswood Avenue
Menlo Park, CA 94025

Mr. H.L. Murphy
Stanford Research Institute
333 Ravenswood Avenue
Menlo Park, CA 94025

Research Triangle Institute
P.O. Box 12195
Research Triangle Park
North Carolina 27709

Dr. Lewis V. Spencer
National Bureau of Standards
Room C313 - Building 245
Washington, D.C. 20234

Mr. Thomas E. Waterman
IIT Research Institute
Technology Institute
Technology Center
10 West 35th Street
Chicago, IL 60616

Mr. Eugene F. Witt
Bell Telephone Laboratories, Inc.
Whippany Road
Whippany, NJ 07981

Mr. William D. Wright
Research Triangle Institute
P.O. Box 12194
Research Triangle Park
North Carolina 27709

Mr. Paul Zigman
Environmental Science Associates
1291 E. Hillsdale Blvd
Foster City, CA 94404

Dr. Carl F. Miller
Center for Planning and Research
Mesilla Park, NM 88047

<p>SHELTER UPGRADING MANUAL: HOST AREA SHELTERS Scientific Service, Inc. Redwood City, CA, March 1980, Contract No. DCPA01-78-C-0215, Work Unit 1127H</p> <p>This manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, and without adequate shelter, crisis relocation planning is not viable.</p> <p>This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings; develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; develops a framework for the practical use of the manual by all persons of interest; and contains charts, pictorial representations, and worksheets that complement and simplify the utility of the manual. The information contained herein is supported by a test program, DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.</p> <p>The manual is in looseleaf format to permit removal of pertinent worksheets and charts for developing upgrading plans for a specific building, and to permit the addition of new and replacement materials as the work progresses.</p>	<p>SHELTER UPGRADING MANUAL: HOST AREA SHELTERS Scientific Service, Inc. Redwood City, CA, March 1980, Contract No. DCPA01-78-C-0215, Work Unit 1127H</p> <p>This manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, and without adequate shelter, crisis relocation planning is not viable.</p> <p>This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings; develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; develops a framework for the practical use of the manual by all persons of interest; and contains charts, pictorial representations, and worksheets that complement and simplify the utility of the manual. The information contained herein is supported by a test program, DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.</p> <p>The manual is in looseleaf format to permit removal of pertinent worksheets and charts for developing upgrading plans for a specific building, and to permit the addition of new and replacement materials as the work progresses.</p>
<p>SHELTER UPGRADING MANUAL: HOST AREA SHELTERS Scientific Service, Inc. Redwood City, CA, March 1980, Contract No. DCPA01-78-C-0215, Work Unit 1127H</p> <p>This manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, and without adequate shelter, crisis relocation planning is not viable.</p> <p>This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings; develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; develops a framework for the practical use of the manual by all persons of interest; and contains charts, pictorial representations, and worksheets that complement and simplify the utility of the manual. The information contained herein is supported by a test program, DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.</p> <p>The manual is in looseleaf format to permit removal of pertinent worksheets and charts for developing upgrading plans for a specific building, and to permit the addition of new and replacement materials as the work progresses.</p>	<p>SHELTER UPGRADING MANUAL: HOST AREA SHELTERS Scientific Service, Inc. Redwood City, CA, March 1980, Contract No. DCPA01-78-C-0215, Work Unit 1127H</p> <p>This manual is one of a series being developed in support of the civil defense concept of crisis relocation planning. One basic element of crisis relocation is shelter protection of the people in the relocated environment, and without adequate shelter, crisis relocation planning is not viable.</p> <p>This manual is designed to be used by planners in host areas. It presents a methodology for evaluating floors, roofs, and openings; develops a variety of ways to provide the necessary structural upgrading for blast and fallout protection; develops a framework for the practical use of the manual by all persons of interest; and contains charts, pictorial representations, and worksheets that complement and simplify the utility of the manual. The information contained herein is supported by a test program, DCPA01-79-C-0231, Work Unit 1127G, and previously developed structural information.</p> <p>The manual is in looseleaf format to permit removal of pertinent worksheets and charts for developing upgrading plans for a specific building, and to permit the addition of new and replacement materials as the work progresses.</p>